

<b>Project Name:</b>	Campsfield, Southwater
<b>Document Reference:</b>	091.0018/ATA/2
<b>Document Name:</b>	Addendum Transport Assessment
<b>Prepared By:</b>	Eleanor Geary (April 2025)
<b>Checked By:</b>	Kim Hammonds (April 2025)
<b>Approved By:</b>	Caroline Duff (April 2025)

Revision Record			
Rev	Date	By	Summary of Changes
2	03.04.25	ERG	Client's comments


#### **Disclaimer**

This document has been prepared in accordance with the scope of Paul Basham Associates Ltd's appointment with its client and is subject to the terms of that appointment. It is addressed to and for the sole use and reliance of Paul Basham Associates clients. Paul Basham Associates accepts no liability for any use of this document other than by its client and only for the purposes, stated in the document, for which it was prepared and provided. No person other than the client may copy (in whole or in part), use or rely on the contents of this document, without the prior written permission of a Director of Paul Basham Associates. Any advice, opinions, or recommendations within this document should be read and relied upon only in the context of the document as a whole. The contents of this document are not to be construed as providing legal, business or tax advice or opinion.

© Paul Basham Associates Limited

## 1. INTRODUCTION

1.1 This Addendum Transport Assessment (ATA) has been prepared by Paul Basham Associates on behalf of Miller Homes to support the residential development of up to 82 units at the site known as Campsfield, Southwater, in support of an Outline planning application with all matters reserved (except access). The site location is shown in **Figure 1**, and a site plan is shown in **Appendix A**.



**Figure 1:** Site Location

1.2 An application was submitted in 2024 (ref: DC/25/0102) to support the development of '*Outline application with all matters reserved except for access for up to 82 dwellings with vehicular and pedestrian accesses, public open space, noise mitigation measures, landscaping, foul and surface water drainage and associated works.*' Following this, West Sussex County Council (WSCC) provided comments on 11<sup>th</sup> March 2025. It was noted that further information was required to aid the application. The formal highway comments are attached as **Appendix B** and are summarised below:

- Inclusion of the vision-led approach within the TA and TP
- WSCC noted they were satisfied with the access strategy put forward
- WSCC noted no concern regarding the modelling
- Consideration provided regarding layout and parking to consider for the Reserved Matters Application

1.3 The aspect which requires additional information, as requested by WSCC, is regarding the vision-led approach. Following receipt of these comments a meeting was also undertaken with WSCC on the 26<sup>th</sup> March 2025, to understand their requirements for the vision-led approach.

1.4 This ATA therefore aims to respond to the additional information requested from WSCC and will provide details regarding the changes to the accommodation schedule, resulting from the updated flood mapping.

1.5 In addition, an updated Framework Travel Plan (FTP) will be submitted to reflect the comments made by WSCC regarding the vision-led approach and therefore should be read in conjunction with this report.

## 2. LAYOUT CHANGES

2.1 The exact unit split proposed for the site will be provided as part of the Reserved Matters Application, although the total units remain at 82. It is noted that following the flood mapping updates the unit mix and their locations have been amended and will now include 1-4 bed units, with the possibility of 4+ units also being included, however this will be confirmed at the reserved matters stage.

2.2 Developing upon this, the road layout of the main spine road for the site has been updated and is shown within the revised site layout plan in **Appendix A**. The access drawings have also been updated to include the red line boundary and these are presented within **Appendix C**.

No other changes have occurred to the access design given that this was agreed by WSCC in their response.

### 3. HIGHWAY COMMENTS

3.1 Aside from the comments regarding the vision-led approach which will be discussed within this section, WSCC were satisfied in principle with the access and visibility, along with noting that the modelling shows no indication that the site will '*give rise to any increase or material change over and above what has previously been agreed*'.

#### Comment 1- Vision-Led Approach to the TA

3.2 WSCC noted that a vision-led approach needs to be incorporated within the TA and TP in line with recent changes to the NPPF (Dec 2024) and Local Plan aspirations.

*'In line with paragraphs 115 and 118 of the National Planning Policy Framework (NPPF) a vision-led transport planning seeks to set out a preferred future in terms of how people will travel and cater for that vision, promoting active and sustainable travel. It seeks to move away from a Predict & Provide approach. Where future travel forecasts are predicated on historical travel data and the assumption that future travel habits will mirror those in the past. The vision-led approach also incorporates more rigorous monitoring, and potentially additional mitigation, should the monitoring show that forecasts do not materialise as envisaged at application stage. WSCC requires that Transport Assessment and Statements are taking a vision-led approach, as is now required by the NPPF'.*

3.3 WSCC asked for additional clarity on how the vision-led approach has been adopted, the key vision and specific targets in the Travel Plan, and additional mitigations methods. Therefore, the Framework Travel Plan has been updated to set out how the vision-led approach is being undertaken at the site and is also set out within this ATA.

3.4 It is understood, with a vision-led approach, that the design should be developed to reflect a desired future, with a focus on sustainable travel and measures, rather than automatically accommodating for an increase in private vehicles. As well as this it is important to allow for adaptation over time, ensuring that uncertainty is accommodated for. Key aspects to consider are:

- Vision driven plan
- Hierarchy users
- Developer responsibility

#### Vision

3.5 The vision for the site is to create an environmentally aware residential development, which integrates with the surrounding area, prioritising travel for pedestrians, cyclists and those using sustainable modes of travel including public transport. With the aim to reduce the

reliance on private vehicles, and encourage walking, cycling and use of public transport, as the preferred method of travel. To ensure this, routes will be integrated into the development for pedestrians and cyclists, to connect into the neighbouring Mulberry Fields development and the surrounding local area, including local amenities and facilities. Creating a sustainable and connected development, making these modes of transport convenient and appealing to current residents within the area, as well as the residents of this development will be key.

- 3.6 Moreover, the development will reduce the need for private car ownership not only by providing connections for pedestrians and cyclists, but through providing ample cycle storage, as well as enhancing sustainability through providing electric vehicle charging points. Along with this, as is discussed in detail within the FTP, the development will promote information on active travel, public transport and car-sharing through the site's Travel Plan Coordinator. Therefore, the site will integrate environmentally friendly practices and infrastructure, while also enhancing the overall quality of life for prospective residents and reducing carbon emissions.
- 3.7 Consequently, the development is deeply committed to operating as sustainably as possible, a vision that is thoroughly articulated, with sustainable credentials of the site comprehensively outlined in the submitted TA and summarised within this ATA.
- 3.8 In line with this vision the target for the development will be a 10% reduction in vehicle trips over a 12-hour weekday period, which will be discussed in the following sections, with further clarification provided within the FTP.

*Vision Based Travel Planning*

- 3.9 Developing on from the vision for the development, at the heart of this sustainable approach is the Framework Travel Plan, submitted in conjunction with this ATA. This plan ensures that all residents are fully informed and aware of the various walking, cycling and public transport offerings available within the site's locale. This strategic document outlines a clear, achievable roadmap for implementing the vision at the site. With a commitment to reducing vehicle trips for residents and visitors at the centre of this plan, through active and sustainable modes of travel becoming the preferred way of travel.

*Hierarchy of Users and Sustainable Travel*

3.10 As noted, within the vision the site will focus on active and sustainable modes of travel, ensuring these are integrated within the development, and promote these as a preferred way of travel over vehicle trips.

3.11 The site itself is situated in an accessible location, with Southwater offering a range of facilities and amenities that benefit prospective residents, whilst Horsham is a 30-minute cycle from the site. As, indicated within the previously submitted Transport Assessment the local area provides a number of footways, cycle routes and Public Rights of Way. These routes also aid movement to the nearest bus stops known as Cripplegate Corner, to enable link-trips and allow for onward journeys to Horsham and further afield if required.

3.12 Furthermore, within the Mulberry Fields development, footways of 2m wide are provided, with a 3m footway/cycleway provided to the north of Mill Straight Roundabout. This provides a direct link to the signalised toucan crossing which is provided to the west of Mill Straight Roundabout which provides a route onto further footways, the Public Rights of Way network and additional bus stops. As well as this, the site itself will provide footways to connect onto the existing provision within Mulberry Fields and the wider highway network, along with a cycleway proposed adjacent to the northern boundary of the proposed site. Therefore, in line with the vision for the site the locality of the site lends itself to ensuring that direct routes for pedestrians, cyclists and public transport, are provided and can be encouraged. In particular, for the short distance trips through promoting these routes as convenient and accessible for daily errands. This is in line with paragraph 15 of the NPPF and aligns with the vision for the site to encourage active and sustainable modes of travel, as the preferred ways of travel.

3.13 Developing upon this, to ensure that active and sustainable modes of travel are at the forefront of residents desired travel modes, as part of the Travel Plan residents will be able to provide feedback on the material provided to them as part of the Travel Plan Works regarding the local area and sustainable modes of travel. Within this feedback residents can note any particular information or routes they would like information on, as well as providing reasoning for their modes of travel. This will provide valuable information to ensure the TP encourages pedestrians, cyclists and public transport as preferred methods of travel for the perspective residents.

3.14 It should also be noted that the accessibility of the site was assessed and considered to be acceptable as part of the Mulberry Fields application (planning ref: DC/14/2582).



## Target

3.15 Following on from the vision, a review of the TRICS historic data has been undertaken, along with a review of the targets and outcomes for Mulberry Fields, to confirm the existing vehicle trip baseline and support a proposed reduction in vehicle trips associated with the proposed development.

### *TRICS Historic Data*

3.16 In order to support and ensure a suitable percentage reduction in vehicle trips, a review of the historic TRICS data has been undertaken. Vehicle trip rates between 2000-2004, 2005-2009, 2010-2014, 2015-2019 and 2020-2024 have been derived from the TRICS database, to understand the reduction in vehicle trips over the 24-year period. The outputs for this are shown in **Appendix D**.

3.17 Whilst the trip rates used in the Transport Assessment are directly reflective of the neighbouring Mulberry Fields development, as the data was collected as part of the Travel Plan work at the site, a broader residential sample size was required to support the historic review. Therefore, the following parameters were used for the review:

- Land use: 'Residential', 'Mixed private and affordable housing' ;
- Sites in England (Excluding Greater London and Wales);
- 0 – 200 Dwellings;
- No travel plan (Aside from 2021-2024 which only had sites with a travel plan)
- Weekday surveys only; and
- Sites in 'Edge of Town Centre', 'Suburban', 'Neighbourhood Centre' locations.
- The assessment period was set from the 1<sup>st</sup> January 2000 to the 31<sup>st</sup> December 2024

3.18 The resultant outputs presented a decrease of 25.85% in 12-hour trips (07:00-19:00) over the 24-year period, this equates to a reduction of approximately 1.07% per year for vehicle trips. Therefore, assuming this trend continues, a 5.35% reduction in vehicle trips for the site over a 5-year monitoring period would be expected given the historic trend.

3.19 Furthermore, as noted within the parameters those surveys included for 2021-2024 all had travel plans, therefore this will have had an impact on vehicle trip rates for these more recently surveyed sites, reflecting an expected reduction in vehicle trips due to the presence of a travel plan.

### Travel Plan

3.20 Developing upon the TRICS data, as presented by the accompanying Framework Travel Plan, a Full Travel Plan will be produced for the site prior to its occupation and implemented for a 5-year period. With an overall aim of a 10% reduction in vehicle trips and an increase in sustainable travel by 10% which is deemed achievable given the size of the development, its proximity to footways, cycleways and bus stops and the evidence provided through the Mulberry Fields development, which itself achieved a 10% reduction in vehicle trips, though it focused on single occupancy rather than all vehicle trip. Further clarification on the sites target is provided within accompanying FTP.

3.21 Mulberry Fields undertook 5-years of Travel Plan Coordination (TPC) works which were completed in July 2024. Along, with this their set target for a 10% reduction in single occupancy vehicle trips was achieved and exceeded. The single vehicle trips were noted at baseline to be 1390 trips over a 12-hour weekday period. This reduced to 570 trips over a 12-hour weekday period at the end of Year 5, presenting a reduction of 820 trips or 59%. This exceeded the target of reducing the trips rates to 1251 trips over a 12-hour weekday period.

3.22 Developing upon this, utilising Mulberry Fields data presents a realistic travel model split for the area given the locality of the site and the access to sustainable modes of travel.

3.23 Therefore, for the overall vision-led approach there could be a total reduction in vehicle trips by around 15% and increase in sustainable travel by 15% based on the TPC works completed at Mulberry Fields and TRICS historic data, however the Framework Travel Plan proposes a 10% reduction for robustness, based on the outcomes noted at Mulberry Fields.

### Residual Impact Assessment

3.24 The detailed TRICS trip generation assessment and modelling assessment, indicates that the proposed development is expected to have a minimal impact on the highway network during peak hours, with WSCC accepting the modelling within their response (**Appendix B**). Furthermore, the site will be accessed from the existing Mulberry Fields development which is considered acceptable by WSCC. Therefore, there should be no severe impact in relation to the cumulative impact associated with the development proposals. In line with NPPF paragraph 16 which states '*Development should only be prevented or refused on highways grounds if there would be an unacceptable impact on highway safety, or the residual*

*cumulative impacts on the road network, following mitigation, would be severe, taking into account all reasonable future scenarios.*

3.25 Remedial measures will be identified within the Framework Travel Plan and could include additional voucher offers or updated monitoring strategies, if required. The 5-year budget for implementing the Travel Plan would be sufficient to ensure that remedial measures could be implemented. Such as if one measure is not working in year 1, there would be budget in year 2 to rectify this and change to new measures if needed. If the five-year target is not achieved, the requirement for remedial measures would be explored with WSCC, based on measures already completed for the site.

### **Mitigation**

3.26 As aforementioned the site will be accessed from the existing Mulberry Fields access. This site undertook 5-years of Travel Plan Coordination (TPC) works which was completed in July 2024. During that time the site had a target to reduce single occupancy vehicle trips by 10%. This was achieved and exceeded, going from 1390 single occupancy trips over a 12-hour weekday period to 570 trips. This assessment provided the baseline upon which the traffic assessment for the proposed site has been created. It is therefore hoped that it presents a robust expectation for the site and that mitigation measures would not be required. Additionally, as aforementioned, the site will implement a Travel Plan which will promote sustainable travel, and should it become apparent that mitigation is required this would be explored with WSCC.

3.27 Furthermore, there is no concern that the development will have a negative impact on the local highway network in accordance with paragraph NPPF 116 and as such mitigation is not expected to be required.

## **4. SUMMARY AND CONCLUSIONS**


4.1 This Addendum Transport Assessment (ATA) has been prepared by Paul Basham Associates on behalf of Miller Homes to support the residential development of up to 82 units at Campsfield, Southwater, in support of an Outline planning application with all matters reserved (except access).

4.2 An application was submitted in 2024 (ref: DC/25/0102), following this West Sussex County Council (WSCC) provided comments on 11<sup>th</sup> March 2025. It was noted that further information was required to aid the application with WSCC requesting further details about

the vision-led approach which needed to be included within the Transport Assessment and Travel Plan to reflect changes made to the NPPF in December 2024.

- 4.3 WSCC also advised they were satisfied in principle with the access and visibility, along with noting that the modelling shows no indication that the site will '*give rise to any increase or material change over and above what has previously been agreed*'.
- 4.4 WSCC asked for additional clarity on how the vision-led approach has been adopted, key vision and specific targets in the Travel Plan, and additional mitigations methods.
- 4.5 The vision for the site is to create an environmentally aware residential development, which integrates with the surrounding area, prioritising travel for pedestrians, cyclists and those using sustainable modes of travel including public transport.
- 4.6 Information has been provided on the vision-led approach, including an assessment of the TRICS historic data and the expectation in relation to the Travel Plan.
- 4.7 We hope WSCC and Horsham District Council find this sufficient to agree to the proposed site in regard to highways.

## Appendix A



## KEY

The site plan illustrates the layout of the residential development area, including the location of residential units, vehicular routes, pedestrian/cycle routes, car parking, private amenity space, and associated landscaping. It also shows the location of supporting infrastructure such as public open space, Local Area of Play, strategic landscaping, and sustainable drainage. The plan includes a network of proposed and existing public rights of way, proposed link roads, and proposed vehicular access points. A 15m buffer from Ancient Woodland is indicated along the southern boundary. The plan also shows the location of proposed pedestrian links and the indicative location of acoustic fences.

PARAMETER PLAN  
02-40(6)10  
1'500 @ 100  
miller homes



MILLER HOMES  
CAMPFIELD, SOUTHWATER  
0240  
ILLUSTRATIVE MASTERPLAN  
0240/01120  
1:500 © AD

CLIENT:  
PROJECT TITLE:  
PROJECT NO.:  
DRAWING TITLE:  
DRAWING NO.:  
SCALE:

THE CORE  
design & construction services  
www.thecoregroup.co.uk



Key:



Site Boundary



Other Land in Landowners Control



CLIENT:  
PROJECT TITLE:  
PROJECT NO:  
  
DRAWING TITLE:  
DRAWING NO:  
SCALE:

MILLER HOMES  
SOUTHWATER, CAMFIELD  
02,18,A  
  
SITE LOCATION PLAN  
02.40(01)00 RevA  
1:1250 @ A2

**miller homes**

## Appendix B

## WEST SUSSEX COUNTY COUNCIL CONSULTATION

<b>TO:</b>	Horsham District Council FAO: Stephanie Bryant
<b>FROM:</b>	WSCC – Highways Authority
<b>DATE:</b>	11 <sup>th</sup> March 2025
<b>LOCATION:</b>	Land at Campsfield Linfield Close Southwater West Sussex RH13 9FR
<b>SUBJECT:</b>	DC/25/0102 Outline application with all matters reserved except for access for up to 82 dwellings with vehicular and pedestrian accesses, public open space, noise mitigation measures, landscaping, foul and surface water drainage and associated works.
<b>DATE OF SITE VISIT:</b>	n/a
<b>RECOMMENDATION:</b>	More Information

### Background

WSCC in its role of Local Highway Authority (LHA) has been consulted on the proposals for highway safety, capacity and access. The development proposals subject to this Outline application are for up to 82 units, of which it is expected that at least 50% will be 2-3 bed units. The site will be accessed from the Mulberry Fields development to the north. This application (DC/14/2582) to the north was a development for 193 units which the LHA raised no objections to in 2014.

The highway aspects of the application are supported by way of a Transport Assessment (TA).

### Vision Led Approach to the TA

In line with paragraphs 115 and 118 of the National Planning Policy Framework (NPPF) a vision-led transport planning seeks to set out a preferred future in terms of how people will travel and cater for that vision, promoting active and sustainable travel. It seeks to move away from a Predict & Provide approach. Where future travel forecasts are predicated on historical travel data and the assumption that future travel habits will mirror those in the past. The Vision-led approach also incorporates more rigorous monitoring, and potentially additional mitigation, should the monitoring show that forecasts do not materialise as envisaged at application stage. WSCC requires that Transport Assessment and Statements are taking a vision led approach, as is now required by the NPPF.

The LHA would therefore request some additional clarity from the applicant on the following matters:

- The applicant should demonstrate how the vision led approach has been adopted through the TA.
- Explicit vision and specific targets in the Travel Plan should be provided. It is noted that the standard target of 10% reduction in vehicle trips has been set

within the Travel Plan. However, no vision is included and clarification should be provided as to whether additional targets are to be set.

- How will any additional mitigation be provided, if the target and vision isn't met? What form will this additional mitigation take?

### **Travel Plan**

Notwithstanding the points above, the submitted travel plan is noted. The applicant should note that WSCC apply an auditing fee to all new travel plans. The travel plan and associated auditing fee would be secured via a s106 agreement. The Travel Plan auditing fees reflect the amount of local authority officer time required to evaluate the initial plan, assess the monitoring data and participate in on-going review and agreement to any amended plans in the future, including post planning once the development is built out and occupied. The costs have been benchmarked against fees charged by other Local Authorities and are considered to proportionate and reflective of the costs incurred

### **Access and Visibility**

The proposed development would be accessed via the neighbouring Mulberry Fields development, with vehicles utilising Centenary Roa. The TA demonstrates visibility splays at the access in line with Manual for Streets (MfS) guidance for a 30mph speed limit in line with the internal speed limit of Centenary Road. Visibility splays from the access appear to be achievable with 2.4m x 43m in the primary direction and to 2.4m x 22m in the secondary direction, reflecting the end of the carriageway.

In terms of servicing delivery, refuse and deliveries will take place from on-site and an internal turning area will be provided to allow access and egress the site in a forward gear within Appendix B of the TA.

In principle the LHA would be satisfied with the access strategy put forward by the applicant.

### **Network Capacity**

Traffic flow information has been provided with the current application within the TS, this has been provided by the applicant on what vehicular activity currently exists at the site. This information considers the permitted and proposed uses. The traffic flow generation is based upon the use of TRICS. TRICS is a database containing surveys of other completed and occupied developments. The database can be refined to use comparably located site uses to forecast potential traffic generation. TRICS is an accepted means of determining traffic generation. Using this data, it is evident that the proposed development would generate 45 AM movements and 29 PM movements.

### **Junction Modelling**

As outlined within the TA Section 6 the applicant has tested the capacity of the following junctions via Junctions 9 software. The assessment takes into account:

- Baseline 2023 (for validation purposes)
- Baseline 2024
- Baseline 2029
- Baseline 2029 + Committed Development
- Baseline 2029 + Proposed Development + Committed Development

The following junctions have been assessed with the Junctions 9 assessment:

- Roman Lane – The modelling highlights the junction would operate within capacity
- Mill Straight South- The modelling highlights the junctions would operate within
- Site Access- The modelling highlights the junction would operate within capacity, there will be a minor increase in queuing however

- Mill Straight North– The modelling highlights the development would have not have an effect on the operation.

Having assessed all the scenario's there is no expectation for this proposal to give rise to any increase or material change over and above what has previously been agreed.

### **Layout and Parking**

Whilst it is acknowledged the application is for Outline consent only the LHA has reviewed the indicative drawings submitted within the TA and would offer the following comments to be taken into consideration:

- Walking and cycling connection central path within the site to existing dev north of it (plus link on the existing site to be provided). Consideration should be given to priority for pedestrians and cyclists across the access road possibly incorporated into a speed control, as latter needed given straight alignment of the spine road.
- Service margin missing from northern edge (this could also be put in as a footway).
- Driveways widths for some of the plots look narrow – recommend 6.0m min width to give decent space to open doors.
- Path running along the northern side of the eastern portion of the site, it is suggested that this be widened to permit walking and cycling.
- Fire and refuse collection should be demonstrated as some of the drives/narrower access roads etc. might make it difficult for access by said vehicles.
- What is proposed main spine road width? Ideally the final design should avoid anything less than 4.8m although private drives could be narrower. However, final widths would probably be dictated by refuse and Fire and Rescue requirements.
- EV cables ducting for parking spaces remote from dwellings.
- The TA acknowledges that parking will be in accordance with LHA parameters.

### **Conclusion**

Having assessed the information submitted within the TA the LHA would request some further information on the point regarding the Vision Led Transport Planning approach as outlined in the first stage of this report.


**Jamie Brown**  
**West Sussex County Council – Planning Services**

## Appendix C


The drawings information and data recorded in this document ("the information") is the property of Paul Basham Associates. This document and the information are solely for the use of the authorised recipient and this document may not be used, copied or reproduced in whole or part for any purposes other than which it was supplied by Paul Basham Associates. Paul Basham Associates makes no representation, undertaken no duty and accepts no responsibilities to any third party who may use or rely upon this document or the information.

#### GENERAL NOTES

1. THIS DRAWING IS INTENDED TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, SERVICES AND SPECIALIST DRAWINGS, DETAILS AND SPECIFICATIONS.
2. ANY VARIATIONS OR DISCREPANCIES BETWEEN THESE DRAWINGS IN TERMS OF DIMENSIONS OR DETAILS SHOULD BE DRAWN TO THE ATTENTION OF THE ARCHITECT AND/OR THE ENGINEER FOR CLARIFICATION.
3. ALL FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. DO NOT SCALE THIS DRAWING.
4. PAUL BASHAM ASSOCIATES ACCEPTS NO RESPONSIBILITY FOR THE ACCURACY OF BACKGROUND INFORMATION PRODUCED BY THIRD PARTIES - THIS MUST BE TREATED AS INDICATIVE ONLY.
5. THIS DRAWING SHOULD ONLY BE USED FOR CONSTRUCTION IF THE PROJECT PHASE IN THE TITLE FRAME BELOW IS SHOWN AS "CONSTRUCTION". PAUL BASHAM ASSOCIATES TAKE NO RESPONSIBILITY FOR CONSTRUCTION WORKS UNDERTAKEN TO DRAWINGS WHICH ARE NOT MARKED UNDER THIS PHASE.
6. VISIBILITY SPLAY DRAWN IN LINE WITH MANUAL FOR STREETS GUIDANCE FOR A 30MPH SPEED LIMIT (2.4M X 43M).



CAR ENTERING AND EXITING THE SITE (1:250)



CAMPSFIELD, SOUTHWATER

VISIBILITY SPLAY AND CAR TRACKING AT ACCESS

Project Phase  
PRELIMINARY

PBA Drawing No:  
091.0018-0002

Revision  
(AT A3)

P03

Project Phase  
PRELIMINARY

PBA Drawing No:  
091.0018-0002

P03


Paul Basham Associates Ltd  
The Botby, Cams Hall Estate, Fareham, PO18 8UJ  
01329 711 000 [www.paulbashamassociates.com](http://www.paulbashamassociates.com)  
info@paulbashamassociates.com

QMS2011/A/6/21/0723/JM

**miller homes**

# PRELIMINARY

DRAWING/DESIGN IS STILL IN DEVELOPMENT  
YOU ARE ADVISED TO MAKE DUE ALLOWANCE



P03	INCLUSION OF RED LINE BOUNDARY	03.04.25	ERG	CID
P02	CLIENT'S COMMENTS	02.12.24	ERG	CID
P01	FIRST ISSUE	22.11.24	ERG	CID
Rev	Description	Date Created	Drawn By	Approved By
		21.11.24	ERG	CID
			Scale	AS INDICATED
				(AT A3)

Revision  
(AT A3)


P03

The drawings, information and data recorded in this document ("the information") is the property of Paul Basmah Associates. This document and the information are sold only for the use of the authorised recipient and his document may not be used, copied or reproduced in whole or part for any purposes other than which it was supplied by Paul Basmah Associates. Paul Basmah Associates makes no representation, undertakes no duty and accepts no responsibilities to any third party who may use or rely upon this document or the information.

## GENERAL NOTES



1. THIS DRAWING IS INTENDED TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, SERVICES AND SPECIALIST DRAWINGS, DETAILS AND SPECIFICATIONS.
2. ANY VARIATIONS OR DISCREPANCIES BETWEEN THESE DRAWINGS IN TERMS OF DIMENSIONS OR DETAILS SHOULD BE DRAWN TO THE ATTENTION OF THE ARCHITECT AND/OR THE ENGINEER FOR CLARIFICATION.
3. ALL FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. DO NOT SCALE THIS DRAWING.
4. PAUL BASHAM ASSOCIATES ACCEPTS NO RESPONSIBILITY FOR THE ACCURACY OF BACKGROUND INFORMATION PRODUCED BY THIRD PARTIES – THIS BEING TREATED AS INDICATIVE ONLY.
5. THIS DRAWING SHOULD ONLY BE USED FOR CONSTRUCTION IF THE PROJECT PHASE IN THE TITLE FRAME BELOW IS SHOWN AS "CONSTRUCTION". PAUL BASHAM ASSOCIATES TAKE NO RESPONSIBILITY FOR CONSTRUCTION WORKS UNDERTAKEN TO DRAWINGS WHICH ARE NOT MARKED UNDER THIS PHASE.

KEY



100

1.1 m	2.35
Overall length	
Overall Width	
Overall Body Height	
Min Body Ground Clearance	
Track Width	
Lock to lock time	
Kerb to Kerb Turning Radius	



## PRELIMINARY

DRAWING/DESIGN IS STILL 'IN DEVELOPMENT'  
YOU ARE ADVISED TO MAKE DUE ALLOWANCE

INCLUSION OF RED LINE BOUNDARY			
P03	CLIENTS' COMMENTS	03.04.25	ERG
P02	FIRST ISSUE	02.12.24	ERG
P01	POI	22.11.24	ERG
Rev	Description	Date	App'd Sustainability Code
21.11.24	Drawn By	Approved By	
	ERG	CID	
		Scale	-

<p>091.0018</p> <p>PBA Drawing No:</p>	<p>091.0018-0003</p>
<p>1:250</p> <p>(AT A3)</p>	<p>Revision P03</p>

MS2011/v8/210723/JM

The diagram illustrates a site plan with several key features:

- Fire Access:** A red line indicates the path for a fire tender to exit the site. A green line shows an alternative route. A cyan box labeled "DC32 Fire Appliance" is positioned near the red line.
- Jumping Station:** A white rectangular area labeled "JUMPING STATION" is located in the bottom right corner.
- Octagonal Areas:** Two octagonal areas are marked with circles in their centers, located in the top right and bottom right sections of the site.
- Numbered Areas:** Several areas are labeled with the number "123" and a triangle symbol, indicating specific zones or equipment locations.
- Text Labels:** The text "FIRE TENDER EXITING THE SITE" is oriented vertically on the left side, and "DC32 Fire Appliance" is located near the bottom right of the red line.

miller homes

Paul BASHAM Associates Ltd  
The Bothy, Cams Hall Estate, Fareham, PO16 8UT  
01329 711 000  
info@paulbashamassociates.com [www.paulbashamassociates.com](http://www.paulbashamassociates.com)

**paulbasham**  
associates

# REFUSE AND FIRE AT ACCESS

Project Name **CAMPSEU D SOUTHWATER**

Paul BASHAM Associates Ltd  
The Bothy, Cams Hall Estate, Fareham, PO16 8UT  
01329 711 000  
info@paulbashamassociates.com [www.paulbashamassociates.com](http://www.paulbashamassociates.com)

Project Name  
CAMPSI  
Project Phase  
PRELIM

## Appendix D

