



NB Site to be cleared of rubbish and debris. Remove or repair all dilapidated fencing. All trees to be managed in line with Arboricultural Survey by Arbtech. Trees and large shrubs to have dead limbs removed and ivy cleared from trunks and canopies. In order for construction to occur around trees, tree protection fencing to be installed in line with BS 5837 Trees in relation to Design, Demolition and Construction, the Arbtech Tree Constraints Plan ref: Arbtech TCP 01 (that shows Root Protection Areas) and a Tree Protection Plan (with construction method statement) to protect the following trees, T01, T03, T04, T06, T07, T08, T11, T25, T26 and G04.