

Potential areas for landscaping

North West preferred placement for trees

Mannings Heath GC - Proposed Landscape Schedules

Individual Trees

Species

Sorbus aucuparia (Mountain Ash)		Standard	1.8m	6
Acer campestre (Field Maple)		Standard	1.8m	4
Betula pendula		Standard	1.8m	6
Fagus sylvatica		Standard	1.8m	5
Quercus Robur		Standard	1.8m	4
Total				25

Wildflower Meadow

Area of wildflower Meadow =1190m2
Sowing rate 3- 5 g per m2

1.4% Achillea millefolium (Yarrow)
1.3% Anthoxanthum odoratum (Sweet Vernal Grass)
4% Campanula rotundifolia (Harebell)
1.3% Digitalis purpurea (Foxglove)
1.3% Endymion non-scriptus (Bluebell)
1.4% Galium verum (Lady's Bedstraw)
1.3% Lotus corniculatus (Birdsfoot Trefoil)
1.4% Plantago lanceolata (Ribwort Plantain)
1.4% Prunella vulgaris (Self-Heal)
1.4% Ranunculus acris (Meadow Buttercup)
1.3% Ranunculus repens (Creeping Buttercup)
2.5% Rumex acetosa (Common Sorrel)
30% Agrostis castellana (Common Bent)
6% Agrostis stolonifera (Creeping Bent)
12.5% Deschampsia flexuosa (Wavy Hair-Grass)
25% Festuca ovina (Sheeps Fescue)
6.5% Poa pratensis (Smooth-Stalked Meadow Grass)

Mannings Heath Golf Club - Proposed Landscape Schedules

Woodland Block Planting

Species

Acer campestre	15%	12	17	37	66
Betula pendula	20%	15	23	50	88
Alnus glutinosa	5%	4	6	12	22
Fagus sylvatica	10%	8	11	25	44
Taxus baccata	5%	4	6	12	22
Prunus avium	15%	12	17	37	66
Quercus robur	25%	19	28	62	110
Pinus Sylvestris	5%	4	6	12	22
Total	100%	77	113	247	438

Project Name: Mannings Heath

Drawing Name: Proposed Landscape Plan

Drawn By: AR

Checked By: BW

Client:

Project No: 0406

Drawing No: 0406.04

Date: 06/07/2026

Scale: 1:200 @ A1

Revision No:



Existing Contours
(0.5m Intervals)

Application Site Boundary

Existing Trees (Retained)
(Refer also to Arboricultural Report)

Existing Hedgerow

Proposed Maintenance Track

Proposed Wildflower Grassland

Proposed Contours
(0.5m Intervals)

Proposed Access Pathway
(Rubber Crumb Finish)

Proposed Mixed Scrub

Proposed Trees

