


- 
1. Thuja (T1) - Removal of low limb to S.East to match remainder of crown. 8m to 0m. Reduction of limb to North o/hanging entrance driveway to match crown. 8m to 5m.

Sycamore (T3)- Removal of Squirrel damaged low limb overhanging footpath to West. 4m to 0m.

Horse Chestnut (T4) - A complicated specification dictated by WSCC Highways (previously submitted) involving cutting back splayed areas for lighting. For the purposes of validation, reduction of Western crown over footpath 7m to 4metres.

2. Please find the Survey for Sycamore (T2) attached attached.
 3. All the tree along this stretch have coalesced to form a group. From the HDC ArcGis map, the trees to be uplifted could range from T49- T65 according to TPO 0440, although I am sure some of the original trees mapped are no longer present, and there are many unprotected trees along this stretch. The proposed work to uplift the canopies to give 2.5m -3metres ground clearance for pedestrians on the footpath. I believe these proposed works would be permissible under a 5 day notice as the reason is to abate an 'actionable nuisance' but have been included in the application to hopefully reduce unnecessary replication of paperwork.
- 