

Understorey brambles and Field Maple to be cut back where required to line 2.5m back from carriageway edge to facilitate maintenance/reinstatement of drainage ditch.



Vegetation including Field Maple, brambles located on eastern end of hedgerow to be cut back (towards wooded boundary post) by no more than 1.5m for reasons of good arboricultural management and to maintain clearance for access/gates.



Two Field Maple trees, tree nos. 19 & 20 per David Archer Associates AMS/TPP Feb 25, to be removed to facilitate maintenance/reinstatement of drainage ditch.



Understorey ivy, brambles, Holly and Hazel to be cut back where required to line 2.5m back from carriageway edge to facilitate maintenance/reinstatement of drainage ditch.