

FOR CONTINUATION – SEE C2070_101

DESIGN SUBJECT TO THE APPROVAL OF:
PLANNING AUTHORITY
BUILDING CONTROL
WATER AUTHORITY

DESIGN SUBJECT TO THE CONFIRMATION OF:
EXTERNAL LEVELS DESIGN
GROUNDWATER DEPTH
ORDINARY WATERCOURSE APPROVAL
LOCATION AND DEPTH OF EXISTING UTILITIES
ROOT PROTECTION AREAS

- STANDARD DRAINAGE NOTES
- DO NOT SCALE FROM THIS DRAWING. REFER TO FIGURED DIMENSIONS ONLY. THE CONTRACTOR SHOULD CHECK ALL DIMENSIONS ON SITE.
 - ALL DIMENSIONS IN MILLIMETRES AND ALL LEVELS ARE IN METERS UNLESS NOTED OTHERWISE.
 - THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECT AND ENGINEERING DETAILS, DRAWINGS AND SPECIFICATIONS.
 - ANY DISCREPANCIES SHOULD BE REPORTED TO THE ARCHITECT AND/OR ENGINEER IMMEDIATELY, SO THAT CLARIFICATION CAN BE SOUGHT PRIOR TO THE COMMENCEMENT OF WORK.
 - BEFORE COMMENCING CONSTRUCTION THE CONTRACTOR MUST CHECK THE INVERT LEVELS OF EXISTING SEWERS TO WHICH CONNECTIONS ARE MADE. IN ADDITION THE CONTRACTOR MUST LOCATE AND DETERMINE INVERT LEVELS OF THE EXISTING SPURS TO WHICH CONNECTIONS ARE PROPOSED. ANY DISCREPANCIES ARE TO BE NOTIFIED TO THE ENGINEER IMMEDIATELY, PRIOR TO CONSTRUCTION.
 - ALL DRAINAGE WORKS SHOULD COMMENCE AT THE PROPOSED DOWNSTREAM CONNECTION POINT. THE WORKS CONTINUING UPSTREAM FOLLOWING CONFIRMATION OF THE TIE-IN INVERT LEVELS TO THE ENGINEER. CONNECTIONS TO MANHOLES OR LARGER SIZED PIPES ETC. SHOULD BE SOFFIT TO SOFFIT UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER, IF THIS IS NOT POSSIBLE INFORM THE ENGINEER IMMEDIATELY.
 - COVER LEVELS SHOWN ARE APPROXIMATE. COVERS AND FRAMES SHALL BE SET TO FINISHED GROUND LEVELS AND FALLS.
 - ALL UN-REFERENCED PIPES ARE TO BE 100mm DIA.
 - ALL PIPES TO BE ADOPTED, OR CONNECTING TO ADOPTED SEWERS, TO BE VITRIFIED CLAY TO BS EN 295 AND BS65 (SWS ONLY), OR CONCRETE PIPES TO BE EN 1916 AND BS5911:PART 1.
 - ROAD GULLY OUTLET PIPES ARE TO BE 150mm DIA. WITH CONCRETE SURROUND AND FLEXIBLE JOINTS. ALL GULLIES SHALL BE FITTED WITH GRADE D400 GRATINGS AND FRAMES TO BS EN124, UNLESS OTHERWISE STATED.
 - ALL ADOPTABLE SEWERS SHALL BE CONSTRUCTED TO THE STANDARDS AND SPECIFICATION LAID DOWN DOWN IN 'SEWERS FOR ADOPTION' 6th EDITION, WITH A VIEW TO ADOPTION UPON COMPLETION OF WORKS.
 - ALL PRIVATE DRAINAGE TO BE IN ACCORDANCE WITH THE BUILDING REGULATIONS APPROVED DOCUMENT PART-H, AND TO THE SATISFACTION OF THE BUILDING CONTROL INSPECTOR.
 - THE CONTRACTOR IS TO KEEP A RECORD OF ANY VARIATIONS MADE ON SITE, INCLUDING THE RELOCATION OF SEWERS OR DRAINS, SO THAT AN AS CONSTRUCTED DRAWINGS CAN BE PREPARED UPON COMPLETION OF THE PROJECT.
 - STUB CONNECTIONS TO ADOPTABLE MANHOLES SHALL BE MADE FROM VITRIFIED CLAY AND CONSIST OF TWO ROCKER PIPES LAID AT THE SAME GRADIENT AS THE UP OR DOWNSTREAM PIPE.
 - IF ANY SUB SOIL DRAINAGE SYSTEMS ARE UNCOVERED DURING THE WORKS CONTACT THE ENGINEER FOR INSTRUCTIONS. SUB SOIL DRAINS ARE TO BE DIVERTED AROUND NEW WORKS AND CONNECTED INTO THE SURFACE WATER.
 - NO PRIVATE AREAS ARE TO DRAIN ONTO ADOPTABLE AREAS AND VICE VERSA.
 - ALL EXISTING MANHOLE COVER'S, GULLIES, ETC. ARE TO BE RAISED/LOWERED TO SUIT NEW LEVELS.
 - IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THE LOCATION AND DEPTH OF ALL EXISTING SERVICES AND UTILITIES THAT MAY BE PRESENT
 - UPON COMPLETION BUT PRIOR TO HANDOVER, CONTRACTOR TO CARRY OUT FULL CCTV SURVEY OF DRAINAGE SYSTEM WHICH IS TO BE REVIEWED BY ENGINEER TO ENSURE SATISFACTORY INSTALLATION
 - PROPRIETARY PRODUCTS TO BE INSTALLED IN FULL ACCORDANCE WITH MANUFACTURER'S GUIDANCE.
 - MANHOLE AND CHAMBER COVER GRADES:
 - 'A15' IN ALL LANDSCAPED AREAS AND ON FOOTPATHS
 - 'B125' IN ALL DRIVEWAYS
 - 'C250' IN PRIVATE PARKING AREAS
 - 'D400' IN CARRIAGEWAY/ACCESS ROAD

COMPULSORY
Remedial works to be carried out on existing Surface Water drainage prior to construction to ensure network continues to function as intended

COMPULSORY
CONTRACTOR TO CONFIRM INVERT LEVEL OF DOWNSTREAM CONNECTION PRIOR TO INSTALLATION OF DRAINAGE
PROPOSED CONNECTION SUBJECT TO TOPOGRAPHICAL SURVEY TO CONFIRM GROUND LEVELS AND ENSURE A CONNECTION IS POSSIBLE

- Site Specific Notes
- The proposed scheme consists of the demolition of outbuildings and construction of a detached dwelling.
 - Onsite infiltration testing failed, with surface water held within the clay layers draining into the trial pit. Groundwater monitoring is currently underway and the well itself was noted to be dry during installation and also dry during follow up visits.
 - It is proposed that surface water runoff is to discharge into an existing drainage network that serves the adjacent Wappingthorn Lodge. The existing network is noted to discharge into an existing pond which connects into the wider watercourse network.
 - The runoff from the site is to be captured into a positive drainage network prior to discharging into the adjacent network at a restricted rate of 0.9/s. The proposed network will make use of bio-retention planters and rainwater harvesting in order to reduce the overall volume of runoff.
 - The foul water is to be treated on site via an STP with a high quality treated effluent which will connect into the pond and discharge into the wider watercourse network.

Prefixed to drawing numbers shall signify the following:-

PL = PLANNING	Shall not be used for contract or construction purposes
P = PRELIMINARY	Shall not be used for contract or construction purposes
T = TENDER	Shall not be used for construction purposes
C = CONSTRUCTION	These are the only drawings that shall be used for construction purposes
R = RECORD	Record of actual completed work

DRAINAGE LEGEND

EXISTING FEATURES

- | | | | | | |
|--|--------|---|--|--------|--|
| | Ex FWD | Existing foul water sewer/drain and manhole | | Ex SWD | Existing surface water sewer/drain and manhole |
| | | Red Line Boundary | | | Blue Line Boundary |

PROPOSED FEATURES

- | | | | | | |
|--|-----|---|--|-----------------|--|
| | FWD | Foul Drainage | | CWD | Combined Drainage |
| | SWD | Surface Water Drainage | | | Combined water inspection chamber (4500) |
| | | Rainwater pipe | | FW | Soil stack (type TBC by architect/m&e engineer) |
| | | Storm water access chamber (3000) | | | Foul water access chamber (3000) |
| | | Storm water inspection chamber (4500) | | | Foul water inspection chamber (4500) |
| | | Storm water catchpit chamber (4500) | | 00.000 | Finished floor level |
| | | Storm water catchpit chamber (4500) | | 1000 4.5m 1:100 | Pipe info - diameter, length, gradient, bedding type |
| | | Extent of permeable paving with porous sub-base | | | |
| | DT | Permavoid distribution tank | | | |
| | | Storm water orifice flow control chamber (5000) | | | |
| | | Bioretention Planter | | | |
- ABBREVIATIONS**
- | | |
|----|---------------------------|
| MH | - MANHOLE |
| IC | - INSPECTION CHAMBER |
| AC | - ACCESS CHAMBER |
| CP | - CATCHPIT |
| BC | - BRAKE CHAMBER |
| RE | - RODDING EYE |
| IL | - INVERT LEVEL |
| SL | - SUMP LEVEL |
| RA | - RESTRICTED ACCESS COVER |
| CL | - COVER LEVEL |
| TL | - TOP OF CELLULAR SA |
| BL | - BASE OF CELLULAR SA |
| FL | - FORMATION LEVEL |

FOR PLANNING ONLY

P-	25.02.26	PRELIMINARY ISSUE	LH	CS	CS
REV	DATE	DESCRIPTION	BY	CHK	APP
CLIENT LEONARD WARNER					
ARCHITECT SCANDIA-HUS					
JOB TITLE WAPPINGTHORN LODGE STEYNING					
DRAWING TITLE DRAINAGE DESIGN SHEET 2					
DRAWN	LH	ENGINEER	C SLADE	CHECKED	CS
DATE	FEB 2026	SCALE @ A1	1:100	APPROVED	CS
JOB No.	C2070	STATUS	P	DRAWING No.	102
				REV.	1