



cont....

'Schedule of Works'

FRONT GARDEN

- a).- The dead Fraxinus ornus (Manna Ash) situated to the lower front Eastern boundary to be climbed and sectionally dismantled down to ground level, *and the resulting stump and root system to then be ground out.*
- b).- The one Cupressus Arozonica (Cypress) situated to the central point of the front garden adjacent to the 'Garden Well', to be climbed and sectionally dismantled down to ground level, *and the resulting stump and root system to then be ground out.*
- c).- The one dead Ivy clad Fraxinus excelsior (Ash) situated along the Southern side boundary edge of the front garden to be climbed and sectionally dismantled down to ground level only.
- d).- Grind out the one twin stemmed existing stump on the lawn area behind the 'Garden Well'.

REAR GARDEN

- e).- Crown lift one small Picea abies (Spruce) situated to the front of the 'Summer House' Building of lower dead Boughs up to some 5 metres in height.
- f).- The one Larix decidua (Larch) situated to the upper central point of the rear garden to be climbed and sectionally dismantled down to ground level, *and the resulting stump and root system to then be ground out.*
- g).- The two dead Ulmus procera (Elm) situated to the rear Western side boundary line to the upper North Western corner of the garden overhanging the Public Footpath and School Playing Field to the rear, both to be climbed and sectionally dismantled down to fence height level.
- h).- The one medium sized Acacia situated to the rear North side border area swapping the surrounding specimen trees, to be climbed and sectionally dismantled down to ground level, *and the resulting stump and root system to then be ground out.*