Dynamika the company with regard to the rainwater harvesting will supply the following:

Water sampling, we would attend, take samples and carry out bacterial analysis in our UKAS accredited laboratory to ensure water is potable. We would provide a certificate with results and should there be a negative result we would advise of what action is required and would attend to carry out the work within 72 hours maximum. E would then retest and provide a new certificate with acceptable results. Cost [redacted] per sample plus vat recommended 4 per year)

2 Annually the tank and associated pipework would be drained down, cleaned and disinfected.
Once completed a certificate of disinfection would be issued. We email client to let them know when we would be attending each year in advance to ensure it is convenient as they would e without water for an hour or so. [redacted]

3 We provide certificates for all work we carry out which we suggest are kept in a logbook that we could supply once we see a copy of the Regulation 6 Risk Assessment. [redacted]

4 We would work with the property owner and supply all documents to them to include in their logbook, they would be responsible for notifying the local planning authority.

The only thing they are unable to do is undertake the Regulation 6 Risk Assessment. Dynamika have stated that this is generally undertaken by the local authority for the DWI. It will be worth pushing back on this