

Generally: All existing timber sash windows to be retained & refurbished and painted in colour tba

New metal gutters to existing house and proposed extension

Existing fanlight to be repaired & refurbished and painted in colour tba

Generally: All existing walls to have pebble-dash stripped off. Walls to be repaired locally. Helibar repairs to be carried out to crack stitch failing brickwork. Replacement bricks and lime mortar where required and re-face with insulating lime render plaster

Front door to be retained & refurbished and painted in colour tba.
Existing modern glass inserts to be replaced with traditional hand-drawn glass

West

1:50 | PROPOSED

MANORWOOD
building on tradition

Suite 114
26 The Hornet
Chichester
West Sussex
PO19 7BB

tel: 01243 201 102
email: enquiries@manorwood.co.uk
web: www.manorwood.co.uk

This drawing is the copyright of Manorwood Construction Ltd.

Do not scale from this drawing.

Exemptions to copyright and scaling apply for Local Authority planning purposes only.

All dimensions must be checked on site prior to commencement of works.

Address
2, School Hill, Warnham, Horsham, RH12 3QN

Drawing
Site:

West

Scale @ A2
1:50

Drawn:	Issued:
06.04.2022	06.04.2022
Drawn By	Checked By
MD	BK

Job No.
2109SC_R4

Drawing No.
2109SC_R4_206

Revisions:
R.0

Status
FOR COMMENT

1m @ 1:
50
100
200
500
1250