



Allan Corfield STRUCTURES

CLIENT:		Glenn & Gemma Cross					Bar Schedule Ref.:		S340_BBS1 - 1 of 1				
PROJECT:		26a Amberley Road, Horsham, West Sussex					Date Prepared:		22/10/2025				
ELEMENT:		Foundation, Ground & First Floor					Prepared By:		WMc				
							Checked By:		PC				
							Version 1.0						
Description	Bar Mark	Type and Size	No. of Mbrs	No. of Bars in Each	Total No.	Length of each bar mm †	Shape Code	A* mm	B* mm	C* mm	D* mm	E/R* mm	Rev. Letter
Core Starter Bars	01	H12	1	55	55	650	00	650					
GF Window Reinf. (Verticals)	02	H16	1	12	12	2700	00	2700					
GF Window Reinf. (Verticals)	03	H16	1	4	4	2425	00	2425					
GF RCP1 (Verticals)	04	H16	2	6	12	3400	00	3400					
GF RCP1 (Links)	05	H10	2	12	24	1100	51	390	90	120	120		
GF RCP2 (Verticals)	06	H16	1	6	6	3400	00	3400					
GF RCP2 (Links)	07	H10	1	12	12	1250	51	465	90	120	120		
Core Corner L-Bars	08	H10	2	15	30	1000	11	500	500				
GF & FF Lintel L1/1 (Btm Bars	09	H16	4	2	8	2175	00	2175					
GF Lintel L2/1 (Btm Bars)	10	H16	1	2	2	2700	00	2700					
GF Lintel L2/1 (Top Bars)	11	H12	1	2	2	2700	00	2700					
GF Lintel L2/1 (Links)	12	H8	1	19	19	825	51	240	90	120	120		
GF Lintel L2/2 (Btm Bars)	13	H16	1	2	2	5250	00	5250					
GF Lintel L2/2 (Top Bars)	14	H12	1	2	2	5250	00	5250					
GF Lintel L2/2 (Links)	15	H8	1	36	36	825	51	240	90	120	120		
FF Window Reinf. (Verticals)	20	H16	1	12	12	2600	00	2600					
FF RCP3 (Verticals)	21	H16	2	6	12	2300	00	2300					
FF RCP3 (Links)	22	H10	2	10	20	1100	51	390	90	120	120		
FF RCP4 (Verticals)	23	H16	1	6	6	2600	00	2600					
FF RCP4 (Links)	24	H10	1	12	12	1250	51	465	90	120	120		
FF Lintel L1/2 (Btm Bars)	25	H16	1	2	2	1575	00	1575					
FF Lintel L2/1 (Btm Bars)	26	H16	1	2	2	4700	00	4700					
FF Lintel L2/1 (Top Bars)	27	H12	1	2	2	4700	00	4700					
FF Lintel L2/1 (Links)	28	H8	1	32	32	825	51	240	90	120	120		