From: [redacted]
Sent: 04 November 2026 16:14
To: Marie.Riggs [redacted]>
Subject: Re: DC/26/1377 - Solar Panels, Lackhams, Lyons Road, Slinford

Dear Marie

Further to our phone call today I can confirm that.

The electric cable for the solar panels will be no more than 40com below ground. The top turf in the field will be taken up to create a narrow 30/40cm trench. which will then be backfilled and the turf replaced. The line of the pipe deliberately coincides with a gap in the existing field hedge. This area will be hand dug. The cable goes under the gravel driveway and into the attached outhouse. This building will house all electrical equipment including batteries.

If you require any further information let me knkow.

Kind regards
[redacted]