


fulcrum | design


Suite 7 Taxiholme
Guildford Road, Bookham
Surrey KT23 4HB
01372 451425
01372 459620
www.fulcrumarchitects.co.uk
info@fulcrumarchitects.co.uk



Planting Schedule	
Ref	Density
A	<i>Luvunga angustifolia</i> Hecox ¹ 5L, 20x50 cm 2m ²
B	<i>Carpinus betulus</i> 5L, 30x40 cm 3m ²
C	<i>Coma alba alba</i> 5L, 20x30 cm 3m ²
D	<i>Ulmus</i> 7.5L, 40x60 cm 1m ²
E	<i>Calluna lilac</i> 2L, 5m ²
Tree Schedule	
	Tree Species
Ref	
1	<i>Carpinus</i> 'nana tortuosa'
2	<i>Magnolia</i> <i>salicifolia</i>
3	<i>Betula</i> <i>pendula</i>

Hard Landscaping Key

- | | |
|---|---|
|  | Ecogrip 350 gravel filled |
|  | 600 x 600mm Burr Paving Slabs |
|  | Random laid Sandstone Paving |
|  | 450 x 450mm Burr Concrete Paving Slabs |
|  | 1800mm high Close boarded fence. All other fences 1500mm high |



Shed providing secure cycle storage and Bin Stores area

Planting

[illegible]

Tree Planting

Trees to be set standard planted in prepared sites 1200 x 300 mm deep. Pit bottom broken up to a depth of 150mm. Trees to be planted at the same depth as grown on the nursery and planted with approved tree burlapping materials, well consolidated to suit soil report recommendations with perforated plastic triangler / ventilation pipe. Immediately after planting, all trees are to be supported with four bamboo stakes and cross bar. Stakes to be softwood, painted chestnut, larch or oak. Straight, free from projections and tapered edge knots and with pointed lower end.

Firmly fix on wharfed side of tree and as close as possible to stem, first, lashed then, secured the firmly but not rigidly to cross bar Remove stems on establishment of trees. Mulching: All trees are to be mulched after planting with Ornamental bark mulch. Mulch or equal approved over an area of 1.2 x 1.2m with the tree in the center. Leave a 10-15cm clear collar of mulch around stem to prevent trunk rot from rotting. The finished level of mulch to be 30mm above adjacent grassed or paved area. Immediately after planting and prior to mulching all trees are to be watered to soil field capacity.

PLANTING SHRUBS / HERBACEOUS PLANTS/BULBS

Shrubs to be planted in that is to be 150mm wider than roots when 19mm spread and 200mm depth. All pit bottoms are to be broken up to a depth of 150mm, incorporating soil amendment / conditioner at 50 g/m² and backfilled with sterile planting stockfilling material and well consolidated. Mulching: All shrub areas to be mulched with Ornamental bark mulch (Melcourt, or equal approved) to a depth of 75mm. The finished level of mulch: 30mm below adjacent grassed or planted areas and all plants to be watered to soil field capacity, prior to mulching.

Turfing

Preparation: All topsoil areas are to be reduced to a fine, firm tilth with good crown structure. Related to a true, even surface, friable and lightly tined but not over compacted. Remove surface stones / earth clods exceeding 10mm.

Turf: All lawn areas to be laid with cultivated turf. Laid within 18 hours of delivery and avoiding laying when persistent cold or drying winds are likely to occur or, as the frost subsides, waterlogged or excessively dry. Turf to be laid in panels laid on previously laid turf with broken joints, well butted up. All newly laid lawns are to be thoroughly water immediately after laying.

Check: that water has penetrated into the soil below.

Watering to be carried out twice monthly for the first two years during the summer months and in times of drought. All maintenance to be carried out in accordance with BS7370-4:1993.

Maintenance

Proposed Landscaping

Brix Ltd

11 Ridgeway Drive, Horsham, RH12 1FX

Site Area	Paper Size	Drawn by	Date	Scale	Drawing No.
	A2	GS	21-01-22	1:200	21-35-10