



Plant Schedule			
Plant name	Size/Girth	Density	Quantity
Hedgerow			
Carpinus betulus	80-100cm	5 plants/Lm (double staggered rows)	260

Spesification

Planting Arrangement:

Hedgerow to be planted in two staggered rows
Rows spaced at 300–330mm apart
Plants within rows spaced at 300–330mm centres
Achieving a minimum density of 5 plants per linear metre

Plant Stock:

Bare root transplants, 80-100cm height
Conforming to BS 3936-1: Nursery Stock
Planted during dormant season (November to March)

Ground Preparation:

Existing vegetation cleared and soil cultivated to 300mm depth
Incorporate organic matter if required
Ensure free-draining but moisture-retentive soil conditions

Planting Method:

Notch or pit planting as appropriate
Roots to be kept moist at all times prior to planting
Firming in to eliminate air pockets

Protection:

Install 60cm spiral guards with canes (or equivalent) to all plants
Particularly required where rabbit/deer presence is likely

Mulching:

75mm depth organic mulch strip (min. 500mm width) or biodegradable mulch mats

Maintenance:

Watering during establishment (first 2 growing seasons)
Weed control to maintain weed-free strip
Replace failures annually (next planting season) to maintain full density
Light formative pruning after establishment to encourage bushy growth

KEY

- 

Existing hedgerow
to be retained
- 

Proposed hedgerow
- 

Existing boundary treatments
3.6m high dark stained closed board fence to be
retained, fixed to steel posts
- 

Existing gate
to be retained



Rev	Date	Description
A	30/03/2026	First issue

THE CAMBRIDGE LANDSCAPER DESIGN AND BUILD LTD
Sheraton House, Castle Street, Cambridge, CB3 0AX
www.cambridge-landscaper.co.uk

Project Title
Moat Cottage, Horsham
Landscape Masterplan

Client
Mchale Contractors

Date
30/03/2026

Scale
1:500@A3

Drawing Revision
2603-dr01-A

