

T1: Silver Birch stands approximately 14 tall with a crown width from centre of 4.5 to 5m all round. After the requested works, there would be a residual height of 11.5 to 12m and a crown width from centre of 3 to 3.5m all round. The required clearance from property would be reached from completing this spec.

T2: Field Maple stands approximately 12 tall with a crown width from centre of 5 to 5.5m all round. After the requested works, there would be a residual height of no less than 9m and a crown width from centre of 3.5m all round. The required clearance from property would be reached from completing this spec.

T3: Whitebeam stands approximately 10 tall with a crown width from centre of 4.5 to 5m all round. After the requested works, there would be a residual height of no less than 8.5m and a crown width from centre of 3.5m all round.

T4: False Acacia stands approximately 14 tall with a crown width from centre of 6 to 6.5m all round. After the requested works, there would be a residual height of no less than 11m and a crown width from centre of 4m all round.

T5: Apple stands approximately 5m tall with a crown width from centre of 3m all round. After the requested works, there would be a residual height of no less than 4m and a crown width from centre of 1.8 to 2m all round.

Works are for general upkeep and maintenance of the site and to minimise debris falling into parking bays.

None of the work would be detrimental, nor affect the amenity values of the area or the trees themselves.

