

897 Coppice Hanger - Plant Schedule

Trees

Number	Species	Specification	Density
211	Acer campestre	tpt : 1+2: 60-80cm:C	3/m²
4	Acer campestre 'Streetwise'	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm	Counted
42	Alnus glutinosa	tpt : 1+2: 60-80cm:C	1/m²
4	Betula pendula	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm	Counted
28	Betula pubescens	tpt : 1+2: 60-80cm:C	1/m²
11	Carpinus betulus	175-200cm: Feathered: 4 brks: 2x: B	1/m²
14	Corylus avellana	tpt : 1+2: 40-60cm:C	1/m²
631	Crataegus monogyna	tpt : 1+2: 60-80cm:C	3/m²
7	Crataegus monogyna	tpt : 1+2: 60-80cm:C	1/m²
7	Fraxinus excelsior	tpt : 1+2: 60-80cm:C	1/m²
7	Ilex aquifolium	cg : 1+2: 20-40cm:C	1/m²
21	Quercus robur	cg : 1+2: 60-80cm:C	1/m²
7	Rosa canina	tpt : 1+2: 40-60cm:C	1/m²
3	Sorbus torminalis	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm	Counted
7	Viburnum opulus	tpt : 1+2: 40-60cm:C	1/m²

Shrubs

Number	Species	Specification	Density
2	Aucuba japonica 'Crotonifolia'	40-60cm: 5L: Bushy: 4 brks: C	1/m²
8	Cornus alba	tpt : 1+2: 40-60cm:C	1/m²
4	Cornus alba 'Elegantissima'	80-100cm: 5L: Branched: 5 brks: RB	1/m²
8	Corylus avellana	tpt : 1+2: 40-60cm:C	1/m²
56	Ilex aquifolium	tpt : 1+2: 20-40:C	3/m²
56	Ligustrum vulgare	tpt : 1+2: 40-60cm:C	3/m²
5	Lonicera pileata	30-40cm: 3L: Bushy: 6 brks: C	3/m²
6	Ribes sanguineum King Edward VII	tpt : 1+2: 40-60cm:C	1/m²
56	Rosa canina	tpt : 1+2: 40-60cm:C	3/m²
3	Rosa rugosa	tpt : 1+2: 40-60cm:C	1/m²
6	Salix caprea	tpt : 1+2: 40-60cm:C	1/m²
56	Viburnum opulus	tpt : 1+2: 40-60cm:C	3/m²

Herbaceous

Number	Species	Specification	Density
10	Alchemilla mollis	2L: Full Pot: C	3/m²
8	Bergenia 'Bressingham White'	2L: Full Pot: C	3/m²
20	Epimedium grandiflorum 'Rose Queen'	2L: Full Pot: C	3/m²
11	Geranium sanguineum	2L: Full Pot: C	3/m²

Wild flower mix
EM8
Mix composed of 20% native wild flowers and 80% slow growing grasses (by weight).
Sowing rate: 5grm/m2
Wild Flowers 20%
0.70% Achillea Millefolium – Yarrow
0.60% Agrimonia eupatoria – Agrimony
0.10% Angelica sylvestris – Wild Angelica
0.20% Betonica officinalis – Betony
3.20% Centaurea nigra – Common Knapweed
1.40% Filipendula ularia – Meadowsweet
1.40% Galium album – Hedge Bedstraw
2.00% Galium verum – Lady's Bedstraw
0.80% Lathyrus pratensis – Meadow Vetchling
0.60% Leontodon hispidus – Rough Hawkbit
1.20% Leucanthemum vulgare – Oxeye Daisy (Moon Daisy)
0.60% Lotus corniculatus – Birdsfoot Trefoil
0.10% Lotus pedunculatus – Greater Birdsfoot Trefoil
1.00% Medicago lupulina – Black Medick
2.00% Plantago lancelata – Ribwort Plantain
0.40% Primula veris – Cowslip
0.80% Prunella vulgaris – Selfheal
1.20% Ranunculus acris – Meadow Buttercup
0.80% Rhinanthus minor – Yellow Rattle
0.60% Rumex acetosa – Common Sorrel
0.30% Sanguisorba officinalis – Great Burnet
0.50% Silene flos-cuculi – Ragged Robin
0.20% Taraxacum officinale – Dandelion
0.30% Vicia cracca – Tufted Vetch

Grasses 80%

4.00% Agrostis capillaris – Common Bent (w)
4.00% Anthoxanthum odoratum – Sweet Vernal-grass (w)
0.80% Carex divulsa subsp. divulsa – Grey Sedge (w)
33.60% Cynosurus cristatus – Crested Dogstail
1.60% Deschampsia cespitosa – Tufted Hair-grass (w)
20.00% Festuca rubra – Red Fescue
3.20% Hordeum secalinum – Meadow Barley (w)
5.60% Phleum bertolonii – Smaller Cat's-tail (w)
5.60% Poa trivialis – Rough-stalked Meadow-grass
1.60% Schedonorus arundinaceus – Tall Fescue

Key

Existing Trees to be retained

Proposed Tree Planting

Proposed Shrub
and Hedge Planting

Wildflower meadow

DAVID ARCHER ASSOCIATES
ARBORICULTURAL CONSULTANCY

Project:	Coppice Hanger Church Hill, Pulborough, West Sussex RH20 1AB
Client:	Purple Pepper Partnership
Drawing:	Planting Plan
Based on:	Architects Layout
Drawing No:	1098-L-02
Rev:	B
08 Apr 2025	
Scale:	1:200@ A1
Drawn:	RP

David Archer Associates.
01273 597796.
david@dave-arboriculture.co.uk

The original of this drawing was produced in colour – a monochrome copy should not be relied upon

©This drawing is copyright & must not be reproduced without consent from David Archer Associates.