




Thank you for your email.

Please find below the additional information requested in relation to the above application.

The proposed works are part of the ongoing cyclical maintenance programme for the trees and are intended to maintain their size, structural integrity and long-term health in accordance with **BS3998:2010 – Tree Work – Recommendations.**

T1 – English Oak

- Current height: Approximately **21 metres**
- Proposed finished height: Approximately **19–19.5 metres**
- Current crown spread: Approximately **10 metres** North, East, South and West
- Proposed crown spread: Approximately **8–8.5 metres** North, East, South and West

Carry out a full crown reduction of approximately **1.5–2.0 metres** throughout the entire crown, reducing back to suitable secondary growth and previous reduction points where evident, whilst retaining the tree's natural shape and balanced crown structure.

In addition, remove **two lower bow limbs** over the garden due to the recent failure of similar limbs from a neighbouring oak. The homeowner has expressed concern regarding the potential risk to children using the area beneath the canopy. All pruning cuts will be made in accordance with **BS3998:2010 – Tree Work – Recommendations.**

T2 – English Oak

- Current height: Approximately **21 metres**
- Proposed finished height: Approximately **19–19.5 metres**
- Current crown spread: Approximately **10 metres** North, East, South and West
- Proposed crown spread: Approximately **8–8.5 metres** North, East, South and West

Carry out a full crown reduction of approximately **1.5–2.0 metres** throughout the entire crown, reducing back to suitable secondary growth and previous reduction points where appropriate, whilst retaining the tree's natural form. The works are proposed as part of the ongoing cyclical maintenance programme in accordance with **BS3998:2010 – Tree Work – Recommendations.**

T3 – English Oak

- Current height: Approximately **21 metres**
- Proposed finished height: Approximately **19–19.5 metres**
- Current crown spread: Approximately **10 metres** North, East, South and West
- Proposed crown spread: Approximately **8–8.5 metres** North, East, South and West

Carry out a full crown reduction of approximately **1.5–2.0 metres** throughout the entire crown, reducing back to suitable secondary growth and previous reduction points as part of the ongoing maintenance programme, in accordance with **BS3998:2010 – Tree Work – Recommendations**.

T4 – English Oak

- Current height: Approximately **21 metres**
- Proposed finished height: Approximately **19–19.5 metres**
- Current crown spread: Approximately **10 metres** North, East, South and West
- Proposed crown spread: Approximately **8–8.5 metres** North, East, South and West

Carry out a full crown reduction of approximately **1.5–2.0 metres** throughout the entire crown, reducing back to suitable secondary growth and previous reduction points whilst maintaining the tree's natural appearance in accordance with **BS3998:2010 – Tree Work – Recommendations**.

T5 – English Oak

- Current height: Approximately **21 metres**
- Proposed finished height: Approximately **19–19.5 metres**
- Current crown spread: Approximately **10 metres** North, East, South and West
- Proposed crown spread: Approximately **8–8.5 metres** North, East, South and West

Carry out a full crown reduction of approximately **1.5–2.0 metres** throughout the entire crown, reducing back to suitable secondary growth and previous reduction points as part of the ongoing cyclical maintenance programme, in accordance with **BS3998:2010 – Tree Work – Recommendations**.

I trust this provides the additional information required to validate the application. Should you require any further details, please do not hesitate to contact me.