PLANTING SCHEDULE

**Trees**

| Number | Species | Abbreviation | Height | Girth | Specification |
|---|---|---|---|---|---|
| 9 | Acer campestre 'Streetwise' | A ca 'S' | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 7 | Acer platanoides | A pl | 300-350cm | 10-12cm | Selected Standard: 4 brks: 2x: RB: Clear Stem 175-200cm |
| 9 | Acer pseudoplatanus | A ps | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem min. 200cm |
| 27 | Alnus glutinosa | A gl | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 16 | Amelanchier lamarckii | A lam | 250-300cm | 10-12cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 65 | Betula pendula | B pe | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 40 | Carpinus betulus | C be | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 4 | Catalpa bignonioides | C bi | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 7 | Malus 'John Downie' | M 'J D' | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 25 | Malus sylvestris | M sy | 250-300cm | 8-10cm | Standard: 4 brks: 2x: B: Clear Stem 175-200cm |
| 10 | Prunus 'Accolade' | P 'A' | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 4 | Prunus 'Kanzan' | P 'K' | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 52 | Prunus avium | P av | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 11 | Pyrus communis | P com | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 44 | Quercus robur | Q r | 250-300cm | 6-8cm | Light Standard: 3 brks: 2x: RB: Clear Stem 150-175cm |
| 32 | Sorbus aria | S ari | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 12 | Sorbus aucuparia | S auc | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 8 | Sorbus aucuparia 'Fastigiata' | S auc 'F' | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |
| 16 | Sorbus aucuparia 'Streetwise' | S auc 'S' | 250-300cm | 8-10cm | Standard: 3 brks: 2x: RB: Clear Stem 175-200cm |

Total :398

**Native Woodland Mix**

| Number | Abbreviation | Species | Height | Specification | Density | Percentage |
|---|---|---|---|---|---|---|
| 185 | A ca | Acer campestre | 80-100cm | 1+1: Transplant - seed raised: B | 1/m² | 10% |
| 185 | B pe | Betula pendula | 80-100cm | 1+1: Transplant - seed raised: B | 1/m² | 10% |
| 94 | C be | Carpinus betulus | 175-200cm | Feathered: 4 brks: 2x: B | 1/m² | 5% |
| 94 | C san | Cornus sanguinea | 40-60cm | 1+1: Transplant - seed raised: Branched: 2 brks: B | 1/m² | 5% |
| 94 | C av | Corylus avellana | 40-60cm | 1+1: Transplant - seed raised: Branched: 2 brks: B | 1/m² | 5% |
| 185 | C mon | Crataegus monogyna | 60-80cm | 1+1: Transplant - seed raised: B | 1/m² | 10% |
| 94 | I a | Ilex aquifolium | 60-80cm | Leader with Laterals: C | 1/m² | 5% |
| 94 | I a | Ilex aquifolium | 125-150cm | Leader with Laterals: RB | 1/m² | 5% |
| 94 | M sy | Malus sylvestris | 60-80cm | 1+1: Transplant - seed raised: B | 1/m² | 5% |
| 185 | M sy | Malus sylvestris | 175-200cm | Feathered: 5 brks: 2x: B | 1/m² | 10% |
| 94 | P pad | Prunus padus | 175-200cm | Feathered: 5 brks: 2x: B | 1/m² | 5% |
| 185 | Q r | Quercus robur | 175-200cm | Feathered: 5 brks: 2x: B | 1/m² | 10% |
| 94 | S auc | Sorbus aucuparia | 175-200cm | Feathered: 5 brks: 2x: B | 1/m² | 5% |
| 94 | T pl | Tilia platyphyllos | 80-100cm | 1+1: Transplant - seed raised: B | 1/m² | 5% |
| 94 | V op | Viburnum opulus | 100-125cm | 1+2: Transplant - seed raised: Branched: 3 brks: B | 1/m² | 5% |

Total :1865 Total :100%

**Native Hedgerow Mix**

| Number | Species | Height | Specification | Density | Percentage |
|---|---|---|---|---|---|
| 102 | Acer campestre | 40-60cm | 1+1: Transplant - seed raised: B | 4/m | 10% |
| 152 | Cornus sanguinea | 60-80cm | 1+1: Transplant - seed raised: Branched: 3 brks: B | 4/m | 15% |
| 152 | Corylus avellana | 60-80cm | 1+2: Transplant - seed raised: Branched: 3 brks: B | 4/m | 15% |
| 152 | Crataegus monogyna | 40-60cm | 1+1: Transplant - seed raised: B | 4/m | 15% |
| 102 | Ligustrum vulgare | 40-60cm | 0/1: Cutting: Branched: 2 brks: B | 4/m | 10% |
| 102 | Rhamnus frangula | 40-60cm | 1+1: Transplant - seed raised: Leader with Laterals: 3 brks: B | 4/m | 10% |
| 102 | Rosa canina | 40-50cm | 1+0: Seedling: Branched: B | 4/m | 10% |
| 152 | Viburnum opulus | 80-100cm | 1+2: Transplant - seed raised: Branched: 3 brks: B | 4/m | 15% |

(Note: Proposed native hedgerows are to be planted as double staggered row) Total :100%

**Native Shrub Mix**

| Number | Species | Height | Pot Size | Specification | Density | Percentage |
|---|---|---|---|---|---|---|
| 3126 | Cornus sanguinea | 60-80cm | | 1+1: Transplant - seed raised: Branched: 3 brks: B | 4/m² | 10% |
| 4674 | Corylus avellana | 60-80cm | 3L | Branched: 3 brks: C | 4/m² | 15% |
| 4674 | Crataegus monogyna | 60-80cm | 3L | 1+1: Transplant - seed raised: Branched: 4 brks: C | 4/m² | 15% |
| 3126 | Ligustrum vulgare | 60-80cm | 3L | Branched: 4 brks: C | 4/m² | 10% |
| 3126 | Rhamnus catharticus | 40-60cm | | 1+1: Transplant - seed raised: Leader with Laterals: 3 brks: B | 4/m² | 10% |
| 4674 | Rosa canina | 40-60cm | 3L | Branched: 5 brks: C | 4/m² | 15% |
| 3126 | Viburnum lantana | 30-40cm | 3L | Branched: 4 brks: C | 4/m² | 10% |
| 4674 | Viburnum opulus | 40-60cm | 3L | Branched: 4 brks: C | 4/m² | 15% |

Total :31200 Total :100%

**Native Shrub Mix for Easement Area**

| Number | Abbreviation | Species | Specification | Density | Percentage |
|---|---|---|---|---|---|
| 2253 | C av | Corylus avellana | Branched: 3 brks: C | 4/m² | 25% |
| 2253 | C mon | Crataegus monogyna | 1+1: Transplant - seed raised: Branched: 4 brks: C | 4/m² | 25% |
| 908 | L vu | Ligustrum vulgare | Branched: 4 brks: C | 4/m² | 10% |
| 1356 | R can | Rosa canina | Branched: 5 brks: C | 4/m² | 15% |
| 908 | S ni | Sambucus nigra | Branched: 3 brks: C | 4/m² | 10% |
| 1356 | V op | Viburnum opulus | Branched: 4 brks: C | 4/m² | 15% |

Total :9034 Total :100%

(Note: Native shrub species **Rosa cania** and **Viburnmum opulus** are **Not** to be planted directly over pipelines.)

**Single Species Hedge**

| Number | Species | Height | Specification | Density |
|---|---|---|---|---|
| 1778 | Carpinus betulus | 60-80cm | 1+1: Transplant - seed raised: B | 4/m |
| 1227 | Ligustrum vulgare | 40-60cm | 0/1: Cutting: Branched: 2 brks: B | 4/m |

Total :3005

(Note: Proposed single species hedges are to be planted as double staggered row)

**Ornamental Shrubs**

| Number | Species | Height | Pot Size | Specification | Density |
|---|---|---|---|---|---|
| 58 | Brachyglottis 'Sunshine' | 30-40cm | 3L | Branched: 4 brks: C | 5/m² |
| 416 | Camellia japonica 'Midnight Magic' | 40-60cm | 3-4L | Leader with Laterals: 2/3 brks: C | 4/m² |
| 377 | Ceanothus thyrsiflorus 'Skylark' | 60-80cm | 3L | Carved: Leader with Laterals: 6 brks: C | 5/m² |
| 411 | Ceanothus thyrsiflorus repens | | 3L | Bushy: 5 brks: C | 5/m² |
| 435 | Choisya 'Aztec Pearl' | 30-40cm | 3L | Bushy: 5 brks: C | 5/m² |
| 436 | Choisya ternata | 40-60cm | 5L | Bushy: 5 brks: C | 5/m² |
| 461 | Cistus x cyprius | 30-40cm | 3L | Bushy: 4 brks: C | 5/m² |
| 105 | Cornus alba 'Sibirica' | 40-60cm | 3L | Branched: 3 brks: C | 5/m² |
| 442 | Cornus sanguinea 'Midwinter Fire' | 40-60cm | 3L | Branched: 4 brks: C | 5/m² |
| 522 | Cornus stolonifera 'Flaviramea' | 60-80cm | 3L | Branched: 4 brks: C | 5/m² |
| 519 | Deschampsia cespitosa 'Goldtau' | | 3L | Full Pot: C | 5/m² |
| 178 | Elaeagnus x ebbingei | 40-60cm | 3L | Branched: 3 brks: C | 4/m² |
| 212 | Erica erigena 'Irish Dusk' | | 2L | Bushy: C | 5/m² |
| 304 | Erica x darleyensis 'White Perfection' | | 2L | Bushy: C | 5/m² |
| 565 | Escallonia 'Apple Blossom' | 40-60cm | 3L | Bushy: 4 brks: C | 5/m² |
| 68 | Euonymus fortunei 'Dart's Blanket' | | 3L | Bushy: 5 brks: C | 5/m² |
| 657 | Fuchsia 'Mrs Popple' | 20-30cm | 3L | Bushy: 5 brks: C | 5/m² |
| 514 | Hebe 'Midsummer Beauty' | 30-40cm | 3L | Bushy: 5 brks: C | 5/m² |
| 131 | Hebe 'Red Edge' | | 3L | Bushy: 5 brks: C | 5/m² |
| 671 | Hebe 'Sapphire' | 20-30cm | 3L | Bushy: 5 brks: C | 5/m² |
| 344 | Hebe 'White Gem' | 30-40cm | 3L | Bushy: 5 brks: C | 5/m² |
| 247 | Hydrangea arborescens 'Annabelle' | 40-60cm | 5L | Branched: 5 brks: C | 5/m² |
| 283 | Hydrangea macrophylla 'Blue Wave' | 40-60cm | 5L | Branched: 5 brks: C | 5/m² |
| 316 | Hydrangea macrophylla 'Madame Emile Mouillière' | 30-40cm | 3L | Branched: 3 brks: C | 5/m² |
| 475 | Hydrangea macrophylla 'White Wave' | 30-40cm | 3L | Branched: 3 brks: C | 5/m² |
| 1070 | Lavandula angustifolia 'Hidcote' | 20-30cm | 3L | Bushy: 5 brks: C | 5/m² |
| 134 | Mahonia aquifolium | 30-40cm | 3L | Branched: 3 brks: C | 5/m² |
| 232 | Mahonia aquifolium 'Apollo' | 20-30cm | 3L | Branched: 2 brks: C | 5/m² |
| 407 | Osmanthus x burkwoodii | 30-40cm | 3L | Bushy: 4 brks: C | 4/m² |
| 87 | Philadelphus 'Manteau d'Hermine' | 30-40cm | 3L | Branched: 4 brks: C | 5/m² |
| 303 | Phlomis fruticosa | 30-40cm | 3L | Branched: 4 brks: C | 5/m² |
| 981 | Potentilla fruticosa 'Elizabeth' | | 3L | Bushy: 4 brks: C | 5/m² |
| 366 | Rosmarinus officinalis 'Prostratus' | | 3L | Bushy: 4 brks: C | 5/m² |
| 13 | Salix hastata 'Wehrhahnii' | 30-40cm | 3L | Branched: 3 brks: C | 5/m² |
| 215 | Santolina chamaecyparissus 'Lemon Queen' | 20-30cm | 3L | Bushy: 7 brks: C | 5/m² |
| 411 | Sarcococca confusa | 30-40cm | 5L | Bushy: 6 brks: C | 5/m² |
| 66 | Sarcococca humilis | 20-25cm | 3L | Bushy: 6 brks: C | 5/m² |
| 496 | Skimmia japonica 'Rubella' | 30-40cm | 3L | Bushy: 3 brks: C | 5/m² |
| 415 | Skimmia x confusa 'Kew Green' | 30-40cm | 3L | Bushy: 3 brks: C | 5/m² |
| 560 | Viburnum davidii | 20-30cm | 3L | Bushy: 3 brks: C | 5/m² |
| 378 | Viburnum opulus 'Compactum' | 30-40cm | 3L | Bushy: 4 brks: C | 5/m² |
| 98 | Weigela 'Victoria' | 30-40cm | 3L | Branched: 4 brks: C | 5/m² |

Total :15399

**Herbaceous and Bulbs**

| Number | Species | Pot Size | Specification | Density |
|---|---|---|---|---|
| 397 | Acanthus mollis | 2L | Full Pot: C | 7/m² |
| 975 | Allium 'Mount Everest' | | Grade 20/+ | 25/m² |
| 780 | Allium sphaerocephalon | 1L | Full Pot: C | 25/m² |
| 33 | Anemone nemorosa | 1L | Full Pot: Sept to April planting: British Native-origin: C | 30/m² |
| 381 | Aster divaricatus | 2L | Full Pot: C | 7/m² |
| 116 | Aster ericoides 'Blue Star' | 2L | Full Pot: C | 7/m² |
| 189 | Bergenia 'Bressingham White' | 2L | Full Pot: C | 7/m² |
| 457 | Calamagrostis x acutiflora 'Karl Foerster' | 3L | Full Pot: C | 7/m² |
| 296 | Carex morrowii 'Ice Dance' | 2L | Full Pot: C | 7/m² |
| 27 | Centaurea dealbata | 2L | Full Pot: C | 7/m² |
| 40 | Cornus stolonifera 'Flaviramea' | 3L | Branched: 4 brks: C | 5/m² |
| 2610 | Crocus speciosus | | Grade 5/6 | 30/m² |
| 260 | Deschampsia cespitosa 'Goldtau' | 3L | Full Pot: C | 5/m² |
| 344 | Dryopteris erythrosora | 1.5-2L | Full Pot: C | 7/m² |
| 420 | Dryopteris wallichiana | 3L | Full Pot: C | 7/m² |
| 277 | Echinacea purpurea | 3L | Full Pot: C | 7/m² |
| 84 | Echinops bannaticus | 2L | Full Pot: C | 7/m² |
| 413 | Echinops ritro | 2L | Full Pot: C | 7/m² |
| 71 | Erica erigena 'Irish Dusk' | 2L | Bushy: C | 5/m² |
| 413 | Filipendula purpurea | 2L | Full Pot: C | 7/m² |
| 851 | Galanthus nivalis | | Grade 6/+ Topsize | 30/m² |
| 640 | Geranium phaeum 'Lily Lovell' | 2L | Full Pot: C | 7/m² |
| 38 | Geranium renardii | 2L | Full Pot: C | 7/m² |
| 369 | Geranium x oxonianum 'Wargrave Pink' | 2L | Full Pot: C | 7/m² |
| 176 | Helleborus argutifolius | 3L | Full Pot: C | 7/m² |
| 146 | Helleborus foetidus | 3L | Full Pot: C | 7/m² |
| 697 | Hosta fortunei 'Albopicta' | 2L | Full Pot: 1 or 2 Buds: C | 7/m² |
| 1048 | Hyacinthus orientalis 'White Pearl' | | Grade 6/8 | 30/m² |
| 182 | Lavandula angustifolia 'Hidcote' | 3L | Bushy: 5 brks: C | 5/m² |
| 139 | Luzula nivea | 2L | Full Pot: C | 7/m² |
| 79 | Mentha spicata | 3L | Full Pot: C | 7/m² |
| 3384 | Narcissus obvallaris | | Grade 10/+ Topsize | 30/m² |
| 283 | Pachysandra terminalis | 2L | Several Shoots: 7 brks: C | 7/m² |
| 34 | Persicaria amplexicaulis 'Firetail' | 2L | Full Pot: C | 7/m² |
| 74 | Phlomis fruticosa | 3L | Branched: 4 brks: C | 5/m² |
| 479 | Rodgersia pinnata 'Superba' | 2L | Full Pot: C | 7/m² |
| 672 | Rudbeckia fulgida sullivantii 'Goldsturm' | 3L | Full Pot: C | 7/m² |
| 493 | Salvia nemorosa 'Caradonna' | 3L | Full Pot: C | 7/m² |
| 177 | Sesleria autumnalis | 3L | Full Pot: C | 7/m² |
| 81 | Stachys byzantina | 5-7.5L | Full Pot: C | 7/m² |
| 157 | Verbascum chaixii | 2L | Full Pot: C | 7/m² |
| 1016 | Verbena bonariensis | 2L | Full Pot: C | 7/m² |
| 285 | Vinca major 'Variegata' | 2L | Several Shoots: 3 brks: C | 7/m² |

Total :20063

**Rose Garden Mix**

| Number | Species | Pot Size | Specification | Density | Percentage |
|---|---|---|---|---|---|
| 7 | Rosa 'Blanche Double de Coubert' | 4L | Budded: Bush: Quality A: C | 5/m² | 15% |
| 11 | Rosa 'Bonica' | 3L | Budded: Bush: Quality A: C | 5/m² | 25% |
| 7 | Rosa 'Buff Beauty' | 4L | Budded: Bush: Quality A: C | 5/m² | 15% |
| 11 | Rosa 'Lilli Marlene' | | B | 5/m² | 25% |
| 9 | Rosa Iceberg | 3L | Branched: 2 brks: C | 5/m² | 20% |

Total :45 Total :100%

**Native Marginal Mix**

| Number | Species | Pot Size | Specification | Density | Percentage |
|---|---|---|---|---|---|
| 708 | Alisma plantago-aquatica | 1L | Full Pot: C | 8/m² | 10% |
| 708 | Baldellia ranunculoides | 1L | Full Pot: June to Sept planting: British Native-origin: C | 8/m² | 10% |
| 708 | Caltha palustris | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 8/m² | 10% |
| 356 | Carex acutiformis | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 8/m² | 5% |
| 708 | Ceratophyllum demersum | 20cc min. | Plug: Established Root: British Native-origin: C | 8/m² | 10% |
| 356 | Glyceria maxima | 1L | Full Pot: Sept to April planting: British Native-origin: C | 8/m² | 5% |
| 356 | Hottonia palustris | 50cc min. | Plug: Established Root min. 2-3 months: April to August planting: British Native-origin: C | 8/m² | 5% |
| 356 | Iris pseudacorus | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 8/m² | 5% |
| 356 | Mentha aquatica | 1L | Full Pot: C | 8/m² | 5% |
| 708 | Menyanthes trifoliata | 1L | Full Pot: Sept to April planting: British Native-origin: C | 8/m² | 10% |
| 708 | Myosotis scorpioides | 1L | Full Pot: Sept to April planting: British Native-origin: C | 8/m² | 10% |
| 356 | Ranunculus flammula | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 8/m² | 5% |
| 708 | Veronica beccabunga | 1L | Full Pot: Sept to April planting: British Native-origin: C | 8/m² | 10% |

Total :7092 Total :100%

**Native Reedbed Mix**

| Number | Species | Pot Size | Specification | Density | Percentage |
|---|---|---|---|---|---|
| 374 | Carex otrubae | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 5/m² | 5% |
| 747 | Glyceria maxima | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 5/m² | 10% |
| 747 | Iris pseudacorus | 50cc min. | Plug: Established Root min. 2-3 months: Sept to April planting: British Native-origin: C | 5/m² | 10% |
| 2607 | Phragmites australis | 50cc min. | Plug: Established Root min. 2-3 months: June to Sept planting: British Native-origin: C | 5/m² | 35% |
| 1492 | Schoenoplectus lacustris | 1L | Full Pot: C | 5/m² | 20% |
| 1118 | Sparganium erectum | 1.5-2L | Full Pot: Sept to April planting: British Native-origin: C | 5/m² | 15% |
| 374 | Typha angustifolia | 1L | Full Pot: British Native-origin: C | 5/m² | 5% |

Total :7459 Total :100%

**NOTE:** Foundations for furniture and equipment, as shown on this drawing, must be designed and constructed by the appropriate structural engineer or manufacturer. Ensure compliance with safety and load-bearing specifications.

References:

- **Landscape general arrangement:** refer to FINC ARCHITECTS drawings H9376-FIN-XX-XX-DR-LA-315000 series for overall landscape general arrangement, hardscape design information.
- **Existing trees and RPA:** Refer to arboricultural report 12072_AIA.001 Rev B and drawing for 12072 TPP 01 Rev D for details.
- **Site Layout and site finishes:** refer to engineer's drawing KJ26-Layout DETAILED / H9376_RSK_22_XX_DR_C_300010-300018 for details.
- **Levels and retaining walls:** refer to engineer's drawing H9376_RSK_22_XX_DR_C_300010-300018 for details.
- **Drainage:** refer to drainage engineer's drawing H9376_RSK_22_XX_DR_C_300021-300059 for details.
- **Water Design:** refer to utility engineer's drawing A127-W-01 Rev K for details.
- **Electric Design:** refer to utility engineer's drawing A127-E-SP-01 Rev I for details.
- **Street Lighting:** refer to lighting engineer's drawing EVO20050742-LD-001-B for details.

| Rev | Date | Amendment | Initials |
|---|---|---|---|
| C04 | 02/11/26 | Issued for discharging planning conditions. | CLB |
| C03 | 21/09/26 | Service information overlay and issued for discharging planning conditions. | CLB |
| C02 | 17/09/26 | Issued for discharging planning conditions. | CLB |
| C01 | 21/08/26 | Issued for WIP. | GS |

**Project:**
NEW PLACE FARM
PULBOROUGH

**Client:**
BARRATT REDROW (SOUTHERN COUNTIES)

**Drawing:**
DETAILED SOFT PLANTING PLAN
PLANTING SCHEDULE

PLANNING

**Drawing no:** H9376-FIN-XX-XX-DR-LA-315026 **Rev:** C04

**Scale@A0:** 1:100 **Date:** AUG26 **Drawn:** SB/RB **Checked:** JM

FINC Architects Ltd
61-63 New London Road | Chelmsford | Essex | CM2 0ND
T: +44 (0)1245 933568
W: www.fincarchitects.com
E: company@fincarchitects.com

Disclaimer:
© FINC Architects Limited holds the copyright to all the information contained within this document and their written consent must be obtained before copying or using the data other than for the purpose it was originally supplied.

All dimensions and measurements to be checked on site.
Do not scale from this drawing. This drawing is to be printed in colour.