SOFTWORKS:

- Medium shrub planting
- Hedge planting
- Existing trees retained
- Existing hedge retained
- Trees proposed
- Specimen shrubs proposed
- Lawn turf
- Gravel area

Cedar Cott

Oakhurst

Martlets

Chenin

Plot 1

Plot 2

Plot 3

Plot 5

Plot 6

NATIVE HEDGE MIX 50.76m

12 No.	Acer campestre	5%	60-90cm
19 No.	Cornus sanguinea	8%	60-90cm
12 No.	Corylus avellana	5%	60-90cm
147 No.	Crataegus monogyna	65%	60-90cm
3 No.	Ligustrum vulgare	1%	60-90cm
3 No.	Malus sylvestris	1%	60-90cm
23 No.	Prunus spinosa	10%	60-90cm
12 No.	Rosa canina	5%	60-90cm

(planted as a double staggered row at 450mm c/s with rows offset 300mm)

NATIVE HEDGE MIX 36.84m

9 No.	Acer campestre	5%	60-90cm
14 No.	Cornus sanguinea	8%	60-90cm
9 No.	Corylus avellana	5%	60-90cm
107 No.	Crataegus monogyna	65%	60-90cm
2 No.	Ligustrum vulgare	1%	60-90cm
2 No.	Malus sylvestris	1%	60-90cm
17 No.	Prunus spinosa	10%	60-90cm
9 No.	Rosa canina	5%	60-90cm

(planted as a double staggered row at 450mm c/s with rows offset 300mm)

NATIVE HEDGE MIX 70.19m

16 No.	Acer campestre	5%	60-90cm
25 No.	Cornus sanguinea	8%	60-90cm
16 No.	Corylus avellana	5%	60-90cm
203 No.	Crataegus monogyna	65%	60-90cm
4 No.	Ligustrum vulgare	1%	60-90cm
4 No.	Malus sylvestris	1%	60-90cm
32 No.	Prunus spinosa	10%	60-90cm
16 No.	Rosa canina	5%	60-90cm

(planted as a double staggered row at 450mm c/s with rows offset 300mm)

NATIVE HEDGE MIX 25.83m

6 No.	Acer campestre	5%	60-90cm
10 No.	Cornus sanguinea	8%	60-90cm
6 No.	Corylus avellana	5%	60-90cm
75 No.	Crataegus monogyna	65%	60-90cm
2 No.	Ligustrum vulgare	1%	60-90cm
2 No.	Malus sylvestris	1%	60-90cm
12 No.	Prunus spinosa	10%	60-90cm
6 No.	Rosa canina	5%	60-90cm

(planted as a double staggered row at 450mm c/s with rows offset 300mm)

NATIVE HEDGE MIX 12.27m

3 No.	Acer campestre	5%	60-90cm
5 No.	Cornus sanguinea	8%	60-90cm
3 No.	Corylus avellana	5%	60-90cm
36 No.	Crataegus monogyna	65%	60-90cm
1 No.	Ligustrum vulgare	1%	60-90cm
1 No.	Malus sylvestris	1%	60-90cm
6 No.	Prunus spinosa	10%	60-90cm
3 No.	Rosa canina	5%	60-90cm

(planted as a double staggered row at 450mm c/s with rows offset 300mm)

PLANT SCHEDULE

Climbers

Number	Species	Height	Specification	Density	Pot Size
48 -	Hedera helix 'White Wonder'	40-60cm	Several Shoots :3/4 brks	3/m²	2L
Total :48 -					

Herbaceous

Number	Species	Spread	Pot Size	Specification	Density
199 -	Bergenia 'Abendglut'		2L	Full Pot	5/m²
82 -	Kniphofia 'Royal Standard'		2L	Full Pot	3/m²
Total :281 -					

Shrubs

Number	Species	Height	Diameter	Pot Size	Specification	Density
89 -	Cornus sanguinea 'Midwinter Fire'	60-80cm		N/A	BR :0/1/1 :Branched :3 brks	2/m²
77 -	Hypericum olympicum 'Citrinum'	20-30cm		3L	Bushy :5 brks	5/m²
26 -	Lavandula angustifolia 'Imperial Gem'	25-30cm		5L	Bushy :7 brks	2/m²
54 -	Mahonia eurybracteata 'Soft Caress'	30-40cm		5L	Bushy :5 brks	3/m²
1 -	Viburnum opulus 'Roseum'	60-80cm		15L	C :Branched :5 brks	Counted
1 -	Viburnum plicatum 'Mariesii'	80-100cm		25L	C :Branched :7/10 brks	Counted
Total :248 -						

Forestry stock (woodland/scrub & native hedges)

Number	Species	Height	Diameter	Pot Size	Specification
46 -	Acer campestre	60-90cm			BR; 1+1; transplant - seed raised
73 -	Cornus sanguinea	60-90cm			BR; 1+1; transplant - seed raised; branched; 3 breaks
46 -	Corylus avellana	60-90cm			BR; 1+2; transplant - seed raised; branched; 3 breaks
568 -	Crataegus monogyna	60-90cm			BR; 1+1; transplant - seed raised
365 -	Ligustrum vulgare	60-90cm			BR; 0/2; cutting; branched; 3 breaks
12 -	Malus sylvestris	60-90cm			BR; 1+1; transplant - seed raised
90 -	Prunus spinosa	60-90cm			BR; 1+1; transplant - seed raised; branched; 2 breaks
46 -	Rosa canina	60-90cm			BR; 1+1; transplant - seed raised; branched; 3 breaks
Total :1246 -					

Standard Trees

Number	Species	Height	Girth	Pot Size	Specification
5 -	Acer campestre	400-450cm	16-18cm		RB :3x :Extra Heavy Standard :Clear Stem min. 200 :5 brks
3 -	Amelanchier 'Robin Hill'	450-625cm	16-18cm		RB :3x :Extra Heavy Standard :Clear Stem min. 200
1 -	Carpinus betulus 'Frans Fontaine'	400-450cm	14-16cm		RB :3x :Extra Heavy Standard :Clear Stem 175- 200cm :5 brks
2 -	Sorbus torminalis	350-425cm	12-14cm		RB :3x : Heavy standard :Clear Stem 175-200cm :5 brks
Total :11 -					

*Note: Size subject to availability, otherwise 8-10cm girth agreed as acceptable by LPA

Seed & Turf

Area	Type	Specification	Density
341m²	Lawn turf	Mix minimum 5 species (predominantly fine blade species)	1/m²
Total :341m²			

General Measurements

Item	Specification	Area
General planting areas	Including well-composted amenity grade (15-65mm) bark mulch	344.3m²
Gravel Area	70mm depth of 40mm shingle over weed control fabric	23.8m²

0m 5m 10m 15m 20m

N

Date	Rev	Rev/Author/Checked By
14-03-24	G	Comments from Horsham DC /AK
19-12-23	F	Plot 1 parking, plot 4 trees removed, plot 6 trees added /AK
08-03-23	E	Planting around pump house, hedges & 1nr tree/AK
19-01-22	D	Comments from Horsham DC; labelling omissions /AK
15-11-21	C	Architect's revised baseplan AK
02-11-21	B	Architect's revised baseplan AK/
17-06-21	A	Architect's revised baseplan AK/
12-04-21	-	Initial submission for comment AK/NC

NIGEL COWLIN
Landscape Assessment & Design
Nigel Cowlin Ltd
Central Stores
George Street
Bures
CO8 5AD
01787 228145
office@nigelcowlin.co.uk
www.nigelcowlin.co.uk

client:
Simon Patience New Homes Ltd.

project:
Greenacres, Storrington

drawing title:
Soft landscape proposals

scale: 1:200 @A1
drawn by: AK
date: 08-04-21
chkd by: NC
drawing number: NC21.659-P-201
revision: G

C:\DROPBOX\NC PROJECT FILES\2021\21.659 GREENACRES, HURSTON LA, STORRINGTON\07 NC PROJECT DRAWINGS\200 P_PLANNING DRAWINGS\21.659-P-201G SOFT