

TIDEY & WEBB LTD

Andrews Hill Yard, Andrews Hill
Billingshurst, West Sussex, RH14 9JT
Tel No (01403) 741673
Email: enquiries@tideyandwebb.co.uk

Our Ref: OL/4670

Mr & Mrs Stevens
Colombine
Bracken Lane
Storrington
RH20 3HS

18th May 2026

Dear Mr & Mrs Stevens

Re: Driveway Reconstruction Works (Porous)

With reference to your recent enquiry and subsequent site meeting, we have pleasure in submitting our quotation for the works as described below.

Quotation

The works concern reconstructing your driveway to create a porous construction. We have allowed for a total area of approximately 140m².

Preparation Works:

The works would include the following items.

- 1) Excavate entire area and existing edging kerbs.
- 2) Cart all arisings away from site to an authorised tip.
- 3) To flower border edges of drive and across entrance, supply and install 150mm x 50mm Bullnose concrete edging kerbs on a bed and haunch of concrete. As discussed, edgings will butt up to the brick retaining wall and will not be laid in front.
- 4) To excavated area, supply and place a Non-Woven Geotextile membrane.
- 5) Supply and lay Type 3 sub-base to a compacted depth of 175mm ready for surfacing.
- 6) Supply and fit 2 No. Recessed manhole covers to replace existing.

Surface Options:

Tarmac

The works would include the following items.

- 1) Supply and lay AC 20mm Open Graded bitumen macadam Binder Course to a compacted depth of 60mm
- 2) Supply and lay AC 10mm SuperDrain Asphalt Surface Course to a compacted depth of 30mm.