TG26 - Mixed Species Native Tree Group ; B, RPA min. 9.3m

T27 - Fraxinus excelsior ; C, RPA min. 8.4m

TG28 - Mixed Species Native Tree Group ; B, RPA min. 3.0m

T29 - Fraxinus excelsior ; C, RPA min. 6.3m
Proposed Tree Surgery Works
The North canopy will require the low branches to be lifted to ensure there is a minimum clearance of 3.5m from the ground.

T30 - Acer pseudoplatanus ; B, RPA min. 3.9m
Proposed Tree Surgery Works
The entire canopy will require the low branches to be lifted to ensure there is a minimum clearance of 3.5m from the ground.

SH31 - Hedgerows and Shrubs ; C, RPA min. 2.7m

T32 - Taxus baccata ; B, RPA min. 5.1m
Proposed Tree Surgery Works
The North canopy will require the low branches to be lifted to ensure there is a minimum clearance of 5m from ground level for access facilitation.

SH46 - Native Shrubs and Scrub; C, RPA min. 1.2m

T33 - Acer pseudoplatanus ; B, RPA min. 6.9m

T34 - Sambucas nigra ; U, RPA min. 3.3m

T38 - Taxus baccata ; B, RPA min. 6.9m

T37 - Taxus baccata ; B, RPA min. 6.0m

T36 - Taxus baccata ; B, RPA min. 4.5m

T35 - Aesculus hippocastanum ;C, RPA min.1.5m

T41 - Fraxinus excelsior ; B, RPA min. 4.2m

T44 - Acer pseudoplatanus ; B, RPA min. 7.5m

T45 - Acer pseudoplatanus ; B, RPA min. 7.8m

T43 - Acer pseudoplatanus ; B, RPA min. 5.4m

T42 - Sambucus nigra ; C, RPA min. 3.0m

T40 - Salix fragilis ; C, RPA min. 2.1m

SH46 - Native Shrubs and Scrub; C, RPA min. 1.2m

T39 - Salix fragilis ; C, RPA min. 2.1m

T47 - Mixed Species Ornamental Tree Group ; B, RPA min. 5.4m

T48 - Aesculus hippocastanum ; B, RPA min. 15m

N

0 1 2.5 5 m

Scale 1:100

Tree Works Removal Plan
Jarvis,Jarvis Lane,Steyning,West Sussex,BN44 3GL

Legend

T02 **Tree, Hedgerow and Shrub Numbers.**

Tree Root Protection Areas
Specified in accordance with *BS 5837:2012 - 'Trees in Relation to Design, Demolition and Construction - Recommendations'*.

Category A Trees
Trees of High Quality and Value to be Retained.

Category B Trees
Trees of Moderate Quality and Value to be Retained.

Category C Trees
Trees of Low Quality and Value to be Retained.

Category U Trees
Trees unsuitable for long term retention.

Existing Trees to be Removed
All operations to be in accordance with *BS3998:2010- 'Tree Works- Recommendations'*

Existing Shrubs and Hedges to be Removed

Proposed Tree Surgery Works
Tree Surgery operations to be in accordance with *BS 3998:2010 - 'Tree Works - Recommendations'*.

Notes:
1. Drawing to be read in colour.
2. For details of existing trees and vegetation refer to: *LLD3620-ARB-SCH-001 - Existing Tree Schedule;*
3. *For assessment of effects of the proposed development on existing trees refer to LLD3620-ARB-REP-001- Arboricultural Impact Assessment and Method Statement.*

PLANNING ISSUE

Rev	Description	Date	Initials
02	Planning Issue	18.03.26	LEB
01	Planning Issue	06.01.26	AS
00	Draft Issue	25.11.25	LEB

LIZARD
Landscape Design and Ecology
The Old Bank, 34 South Street, Tarring, Worthing, West Sussex, BN14 7LH
T. 01903 216033 E. lizardlandscape@btconnect.com W. lizardlandscapeecology.com

Client
Gordon Sutherland
Project Title and Location
Jarvis
Jarvis Lane, Steyning, West Sussex, BN44 3GL
Drawing Title
Tree Works Removal Plan

Scale	*Drawn*	*Approved*	*Date*
1:100@A1	LEB	GO	25/11/2025

Drawing No LLD3620-ARB-DWG-032
Revision 02