Project: **LOWER BEEDING**

EXTERNAL MATERIALS SCHEDULE

Revision **FINAL**

PLOT NO	HOUSE TYPE	HOUSE WALL MATERIALS			FEATURE BRICK		HOUSE ROOF MATERIALS	EXTERNAL JOINERY	RW GOODS	OUTBUILDING MATERIALS		GARDEN WALL BRICK
		BRICK	HUNG TILE	BOARDING	HEAD	CILLS	TILE			WALLS	ROOF	
1	2A AFF	B1	T3	-	-	-	T1	W1	R1	-	-	-
2	1BF AFF 1	B1	T3	-	-	-	T1	W1	R1	-	-	-
3	1BF AFF 2	B1	T3	-	-	-	T1	W1	R1	-	-	-
4	3A AFF	B1	-	C1 (FULL)	-	-	T2	W1	R1	-	-	-
5	2A AFF	B1	-	C1 (FULL)	-	-	T2	W1	R1	-	-	-
6	2A AFF	B1	-	-	-	-	T1	W1	R1	-	-	-
7	2A AFF	B1	-	-	-	-	T1	W1	R1	-	-	-
8	3A AFF	B1	T3	-	-	-	T1	W1	R1	-	-	-
9	3A	B1	-	-	B2	B2	T2	W1	R1	B1	T1	B1
10	2A	B1	-	-	B2	B2	T2	W1	R1	B1	T1	B1
11	4B	B1	T3	-	-	-	T1	W1	R1	-	-	B1
12	4B	B1	T3	-	-	-	T1	W1	R1	-	-	B1
13	3A	B1	-	C1 (FULL)	-	-	T2	W1	R1	B1	T2	-
14	2A	B1	-	C1 (FULL)	-	-	T2	W1	R1	-	-	-
15	3C	B1	T3	-	-	-	T1	W1	R1	B1	T1	-
16	4A	B1	T3	-	-	-	T1	W1	R1	B1	T1	-
17	2B	B1	-	-	B2	B2	T2	W1	R1	B1	T2	-
18	2B	B1	-	-	B2	B2	T2	W1	R1	-	-	-
19	3B	B1	-	C1 (FULL)	-	-	T2	W1	R1	B1	T2	-
20	3C	B1	T3	-	-	-	T1	W1	R1	B1	T1	-
21	3C	B1	T3	-	-	-	T1	W1	R1	-	-	B1
22	4B	B1	T3	-	-	-	T1	W1	R1	-	-	

MATERIALS KEY

BRICK	**B1**	**FLB First Quality Multi**
	B2	**Wienerberger Warnham Red**
TILE	**T1**	**Redland Brown Plain**
	T2	**Redland Charcoal Grey Plain**
	T3	**Redland Antique Red Plain**
BOARDING	**C1**	**Hardie Plank - Cedar - Sail Cloth**
RAINWATER GOODS	**R1**	**Black uPVC**
WINDOWS	**W1**	**White uPVC**

Notes

FULL denotes plot fully boarded above plinth / FIRST denotes weatherboarded to first floor only