

Contractors are not to scale dimensions from this drawing

Revision Date

Rev A geotextile membrane and gravel drainage layer removed 13.8.26

Ensure that a 120mm collar should be left free of mulch to prevent the stems/trunks from rotting

RRURB1A RootRain Urban irrigation system installed around the guyed root ball Ensure inlet is slightly above finished surround level (by GreenBlue Urban or similar approved)

Natural larch, ash or chestnut timber stake.

Rubber tree tie

Approved topsoil - 300mm depth

75mm woodchip mulch, 5-40mm grade

100mm approved top soil to grass areas, and min 400mm approved topsoil to shrub beds.

SASDMB Deadman Arborguy strapped anchor system (by GreenBlue Urban or similar approved).

Break up bottom of tree pit to 200mm depth

Approved sub-soil - 300mm depth

landscape perspective
Chartered Landscape Architects

Fowlers, Broxmead Lane,
Haywards Heath,
West Sussex
RH17 5JH

M: 07894 075577
www.landscapeperspective.co.uk

Client
WT Lamb Holdings Ltd

Project
Broomers Hill Industrial Park

Title
Tree Pit Details Sheet 3 of 3

Status:
for planning

Scale 1/25 @ A4	Drawn AR	Date May 2026
Job number 1810	Drawing number L90-304	Revision A

Copyright Landscape Perspective Ltd

TP04

Standard tree planting in grass / planting beds
Scale 1:25@ A4

