


Schedule of Materials:

- **Roof Finish:** strip and re-slatting including 500x250mm natural Glendyne slates
- **Render Work:** 2 coat work. Moisten surface but do not saturate and form base scratch coat in 1:2:9 OPC not Mastercrete:hydrate bag lime:aggregate to pass at 2mm sieve worked in well to mortar joints and abutments to 18mm thickness. Apply finish coat to an approved sample to match the existing seamlessly in colour and texture. Trowel off and work surface as required to match existing.
- **Rain Water Goods:** 125x100mm approx. moulded cast iron gutter placed on ledge at top of wall with timber back upstand closing off rafter feet. Finsihed in Blackburn or Rustolin primer, and paint 2 undercoat and two gloss coats to match existing.
- **Window:** cut out rotten timber of casement and repair locally. Treat timbers and apply oil paint finish. Replace any damaged window light in 4mm clear float glass.



South Elevation, Central - Proposed Repairs



SCALE BAR 1:100

Do not scale from this drawing. Figured dimensions only to be taken. Check all dimenions prior to setting out. Report all discrepancies to the Architect.

Revisions

Robin Nugent Architects

Chartered Architects ©
Castle Barn Sedgwick Horsham
West Sussex RH13 6QJ

T: 01403 734858 F: 01403 738368
E: robin@robinnugentarchitects.co.uk
W: www.robinnugentarchitects.co.uk

Client:

The Trustees of St Hugh's
Charterhouse

Project:

The Guest House
St Hugh's Monastery

Drawing Title:

South Elevation - proposed repairs

Scale:

1:100
@A3

Date:

Mar 25

Drawn by:

RWN

Drawing No:

22820/221

Revision:

< Original size 60mm - A3 at full size >